



March 23, 2001

State of Utah
Division of Oil, Gas & Mining
Attn: Brad Gill
1594 West North Temple - Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Application for Permit to Drill Well No: 13A-22-8-17, 14-22-8-17,
15-22-8-17, and 16-22-8-17.

Dear Brad:

Enclosed find APD's on the above referenced wells. If you have any questions, feel free to give either Brad or myself a call.

Sincerely,

Mandie Crozier
Permit Clerk

mc
enclosures

cc: Jon Holst
Denver office well file
Pleasant Valley well file

RECEIVED

MAR 26 2001

**DIVISION OF
OIL, GAS AND MINING**

001

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK **DRILL** ☒ **DEEPEN** ☐
1b. TYPE OF WELL
OIL ☐ GAS ☐ SINGLE ☐ MULTIPLE ☐
WELL ☒ WELL ☐ OTHER ☐ ZONE ☒ ZONE ☐

2. NAME OF OPERATOR
Inland Production Company

3. ADDRESS OF OPERATOR
410 - 17th Street, Suite 700, Denver, CO 80202 Phone: **(303) 893-0102**

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. *)
At Surface **SW/SE** **2056' FEL 910' FSL**
At proposed Prod. Zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
Approximately 11.66 miles southeast of Myton, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also t
Approx. 910' f/lse line & 910' f/unit line
16. NO. OF ACRES IN LEASE **1202.78**
17. NO. OF ACRES ASSIGNED TO THIS WELL **40**

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT.
Approx. 1403'
19. PROPOSED DEPTH **6500'**
20. ROTARY OR CABLE TOOLS **Rotary**


21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5168' GR
22. APPROX. DATE WORK WILL START*
3rd Quarter 2001

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH	QUANTITY OF CEMENT
Refer to Monument Butte Field SOP's Drilling Program/Casing Design				

Inland Production Company proposes to drill this well in accordance with the attached exhibit

The Conditions of Approval are also attached.



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM : If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone.
If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED *Bo Macdon* TITLE **Operations Manager** DATE **03/22/2001**

(This space for Federal or State office use)

PERMIT NO. 43-013-32240 APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those lands in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY *Bradley G. Hill* TITLE **BRADLEY G. HILL** DATE 12-16-02
ENVIRONMENTAL SCIENTIST III



**Federal Approval of this
Action is Necessary**

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

LOCATED IN THE SW1/4 OF THE SE1/4 OF
SECTION 22, T8S, R17E, S.L.B.&M.

CANVAS BACK #15-22-8-17



SCALE: 1"=1000'




SURVEYOR'S CERTIFICATE


THE GENERAL LAND OFFICE
(G.L.O.) PLAT WAS USED FOR
REFERENCE AND CALCULATIONS,
AS WAS THE U.S.G.S. MAP.

**THIS SURVEY WAS PERFORMED
USING GLOBAL POSITIONING
SYSTEM PROCEDURES AND
EQUIPMENT. THE BEARINGS
ARE BASED ON WGS84 DATUM.**

I HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM FIELD NOTES OF AN ACTUAL SURVEY PERFORMED BY ME, DURING WHICH THE SHOWN MONUMENTS WERE FOUND OR RE-ESTABLISHED.



**JERRY D. ALLRED, PROFESSIONAL LAND SURVEYOR,
CERTIFICATE NO. 148951, STATE OF UTAH**



JERRY D. ALLRED & ASSOCIATES
SURVEYING CONSULTANTS

121 NORTH CENTER ST.--P.O. BOX 975
DUCESNE, UTAH 84021
(435) 738-5357

REV 17 MAR 2001
12 MAR 2001

84-121-081

Memorandum of Surface Use Agreement

KNOW ALL MEN BY THESE PRESENTS:

That the Brad and JoAnn Nelson Family Trust and the Ethan Lee and Louise Nelson Family Trust, both of P.O. Box 638, Roosevelt, Utah 84052, hereinafter called "Owners," and Inland Production Company, of 410 17th Street, Suite 700, Denver, Colorado 80202, hereinafter called "Inland," have executed a Wellsite Surface and Damage Agreement and an Easement and Right-of-Way, dated December 2, 2002, hereinafter referred to as "Agreement." That Agreement grants Inland certain rights to enter upon and utilize the surface as described below. The terms of which the parties agree as follows:

Inland owns or controls rights and interests in United States Oil and Gas Leas UTU-77233, which covers the following described lands situated in Duchesne County, Utah:

Township 8 South, Range 17 East, SLM
Section 22: SE/4 SW/4 and S/2 SE/4


By virtue of the Agreement referenced above, Owners and Inland have reached an understanding in settlement of disputes on all claims for use of the surface and damage to crops and interruption or interference with agricultural improvements arising from Inland's drilling, completion and production activities and operations for wells, and have also agreed to the measure of settlement for continuing and additional operations by Inland in the area on surface owned or controlled by Owners.

The Agreement shall remain in effect for so long as the drilling, production and development activities continue and all payments and conditions pursuant thereto have been timely paid and honored or terminated by mutual agreement between Owners and Inland. Said Agreement contains terms and provisions other than those herein stated. Executed copies of said Agreement, which sets forth the precise terms thereof, are in the files of the Owners and Inland.

This document is filed to secure all rights, which are accorded through notice as if the Agreement itself had been recorded.

Executed this 12th day of December 2002.

INLAND PRODUCTION COMPANY


 Jeff Fandrich, Attorney-in-Fact

CORPORATE ACKNOWLEDGEMENT

STATE OF COLORADO)
)ss.
 CITY AND COUNTY OF DENVER)

On this 12th Day of December 2002, before me, the undersigned Notary Public in and for the County and State aforesaid, personally appeared Jeff Fandrich, to me known to be the identical person who signed the name and maker thereof to the within and foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same a his free and voluntary act and deed, and as the free and voluntary act and deed of said corporation, for the uses and purposes therein set forth.

Given under my hand and seal the day and year last above written.

My Commission Expires: 8/29/05


 Notary Public

**INLAND PRODUCTION COMPANY
CANVASBACK #15-22-8-17
SW/SE SECTION 22, T8S, R17E
DUCESNE COUNTY, UTAH**

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta	0' – 1640'
Green River	1640'
Wasatch	6500'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1640' – 6500' - Oil

4. PROPOSED CASING PROGRAM

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

Please refer to the Monument Butte Field SOP. See Exhibit "F".

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

Please refer to the Monument Butte Field SOP.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Please refer to the Monument Butte Field SOP.

8. TESTING, LOGGING AND CORING PROGRAMS:

Please refer to the Monument Butte Field SOP.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 2000 psi. It is not anticipated that abnormal temperatures will be encountered.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

Please refer to the Monument Butte Field SOP.

**INLAND PRODUCTION COMPANY
CANVASBACK #15-22-8-17
SW/SE SECTION 22, T8S, R17E
DUCHESNE COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Inland Production Company well location site Canvasback # 15-22-8-17 located in the SW 1/4 SE 1/4 Section 22, T8S, R17E, Duchesne County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.6 miles \pm to the junction of this highway and UT State Hwy 53; proceed southerly along Hwy 53 – 6.8 miles to the junction of an existing paved road to the east. Proceed easterly along this road 2.5 miles to the junction of an existing paved road to the east. Proceed south easterly along this road 0.8 miles to the beginning of the proposed access road of the Canvasback 15-22-8-17.

2. PLANNED ACCESS ROAD

Please refer to Monument Butte Field Standard Operating Procedure (SOP).
See Topographic Map "B" for the location of the proposed access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "D".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

Please refer to the Monument Butte Field Standard Operating Procedure (SOP).

5. LOCATION AND TYPE OF WATER SUPPLY

Please refer to the Monument Butte Field SOP. See Exhibit "C".

6. SOURCE OF CONSTRUCTION MATERIALS

Please refer to the Monument Butte Field SOP.

7. METHODS FOR HANDLING WASTE DISPOSAL

Please refer to the Monument Butte Field SOP.

8. ANCILLARY FACILITIES

Please refer to the Monument Butte Field SOP.

9. **WELL SITE LAYOUT**

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, pipe racks, trailer parking, spoil dirt stockpile(s), and Surface material stockpile(s).

10. **PLANS FOR RESTORATION OF SURFACE**

LandOwner has requested that the well pad be left as is with no rehabilitation after plugging the well.

11. **SURFACE OWNERSHIP** – Brad Nelson.

12. **OTHER ADDITIONAL INFORMATION**

The Paleontological Resource Survey and Archeological Survey have been waived by the landowner. **Refer to Exhibit "G".**

13. **LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION**

Representative

Name: Brad Mecham
Address: Route #3 Box 3630
Myton, Utah 84052
Telephone: (435) 646-3721

Certification


Please be advised that INLAND PRODUCTION COMPANY is considered to be the operator of well #15-22-8-17 SW/SE Section 22, Township 8S, Range 17E: Lease UTU-77233 Duchesne County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4488944.

I hereby certify that the proposed drillsite and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Inland Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

3/22/01

Date


Brad Mecham
Operations Manager



TOPOGRAPHIC MAP "A"


JERRY D. ALLRED AND ASSOCIATES
121 NORTH CENTER STREET
P.O. BOX 975
DUCHESSNE, UTAH 84021
(435) 738-5352



INLAND PRODUCTION CO.
LOCATION X-SECTION PLAT
CANVAS BACK #15-22-8-17
SECTION 22, T8S, R17E, S.L.B.&M.

12 MAR 2001

84-121-081



TOPOGRAPHIC MAP "B"












JERRY D. ALLRED AND ASSOCIATES
121 NORTH CENTER STREET
P.O. BOX 975
DUCESNE, UTAH 84021
(435) 738-5352

SCALE: 1"=2000'

INLAND PRODUCTION CO.
LOCATION X-SECTION PLAT
CANVAS BACK #15-22-8-17
SECTION 22, T8S, R17E, S.L.B.&M.

12 MAR 2001

84-121-081

-  INJ
-  WTR
-  SWD
-  OIL
-  GAS
-  DRY
-  SHUTIN
-  SUSPENDED
-  ABND
-  Injection Stations
-  Unit Sections




4817th Street Suite 700
Denver, Colorado 80202
Phone (303) 891-0102

UINTA BASIN

Druckerei & Versand Center, U.S.A.

Date: 11-11-09

NA.



INLAND PRODUCTION COMPANY

WELL LOCATION PLAT

CANVAS BACK #15-22-8-17

LOCATED IN THE SW1/4 OF THE SE1/4 OF SECTION 22, T8S, R17E, S.L.B.&M.





EXHIBIT E
REFERENCE POINTS

170' ON 3 CENTERLINE = 5170.0'
115' ON 5 CENTERLINE = 5173.7'
190' ON 7 CENTERLINE = 5167.1'

12 MAR 2001

84-121-081




JERRY D. ALLRED & ASSOCIATES
SURVEYING CONSULTANTS

121 NORTH CENTER ST.--P.O. BOX 975
DUCHESNE, UTAH 84021
(435) 738-5357


INLAND PRODUCTION CO.

LOCATION X-SECTION PLAT
CANVAS BACK #15-22-8-17
SECTION 22, T8S, R17E, S.L.B.&M.


1" = 20'
X-SECTION
SCALE
1" = 50'




STA 3+10



STA 2+45



STA 1+65



STA 0+00

EXHIBIT E-1

APPROXIMATE QUANTITIES

CUT: 4340 CU. YDS. (LOCATION)

CUT: 700 CU. YDS. (PIT)

FILL: 3600 CU. YDS.

JERRY D. ALLRED AND ASSOCIATES

121 NORTH CENTER STREET

P.O. BOX 975

DUCHESNE, UTAH 84021

(435) 738-5352

12 MAR 2001

84-121-081

RAM TYPE B.O.P.


Make:

Size:

Model:

2-M SYSTEM

Page 4




2" Minimum

AL TO CLOSE
Annular BOP = _____

Ramtype BOP
_____ Rams x _____ = _____

= _____ Gal.

_____ x 2 = _____ Total Gal.



2" Minimum

2" Minimum

2" Minimum

2" Minimum

Rounding off to the next higher
increment of 10 gal. would require
_____ Gal. (total fluid & nitro volume)

EXHIBIT F

EXHIBIT G

Canvasback 15-22-8-17
SW/SE Sec. 22, T8S, R17E
Lease #UTU-77233

ARCHAEOLOGICAL REPORT WAIVER

For the above referenced location; Brad Nelson, the Private Surface Owner.
(Having a Surface Owner Agreement with Inland Production Company)
Brad Nelson, representing this entity does agree to waive the request from
the Bureau of Land Management for an Archaeological/Cultural Survey.
This waiver hereby releases Inland Production Company from this request.

Brad Nelson *3-22-01*
Brad Nelson Date
Private Surface Owner

Brad Mecham *3-7-01*
Brad Mecham Date
Inland Production Company

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 03/26/2001

API NO. ASSIGNED: 43-013-32240

WELL NAME: CANVASBACK 15-22-8-17

OPERATOR: INLAND PRODUCTION (N5160)

CONTACT: BRAD MECHAM

PHONE NUMBER: 303-893-0102

PROPOSED LOCATION:

SWSE 22 080S 170E

SURFACE: 0910 FSL 2056 FEL

BOTTOM: 0910 FSL 2056 FEL

DUCHESNE

MONUMENT BUTTE (105)

LEASE TYPE: 1-Federal

LEASE NUMBER: UTU-77233

SURFACE OWNER: 4-Fee

PROPOSED FORMATION: GRRV

INSPECT LOCATN BY: / /

Tech Review

Initials

Date

Engineering

Geology

Surface

RECEIVED AND/OR REVIEWED:

☒ Plat☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. 4488944)☒ Potash (Y/N)☒ Oil Shale (Y/N) *190-5 (B) or 190-3☒ Water Permit

(No. MUNICIPAL)

☒ RDCC Review (Y/N)

(Date:)

☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

R649-2-3. Unit CANVASBACK (GR)

R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 225-3 *Unit & E.h. Rec.

Eff Date: 9-23-98

Siting: Statewide Rules Suspended

R649-3-11. Directional Drill

COMMENTS:

Need Presite (4-4-01)

Mon. Butte Field Sol, separate file.

STIPULATIONS:

1- STATEMENT OF BASIS

2- FEDERAL APPROVAL




OPERATOR: INLAND PROD CO. (N5160)

SEC. 22 T8S. R17E.

FIELD: MONUMENT BUTTE (105)

COUNTY: DUCHESNE

CAUSE: 225-3 / 9-23-98



- | WELLS | | UNIT STATUS | | FIELD STATUS | |
|-------|---------------------|-------------|--------------|--------------|-----------------|
| ✓ | GAS INJECTION | □ | EXPLORATORY | □ | ABANDONED |
| • | GAS STORAGE | □ | GAS STORAGE | □ | ACTIVE |
| × | LOCATION ABANDONED | □ | NF PP OIL | □ | COMBINED |
| ⊙ | NEW LOCATION | □ | NF SECONDARY | □ | INACTIVE |
| ◊ | PLUGGED & ABANDONED | □ | PENDING | □ | PROPOSED |
| * | PRODUCING GAS | □ | PI OIL | □ | STORAGE |
| * | PRODUCING OIL | □ | PP GAS | □ | TERMINATED |
| • | SHUT-IN GAS | □ | PP GEOTHERML | □ | COUNTY BOUNDARY |
| • | SHUT-IN OIL | □ | PP OIL | □ | SECTION LINES |
| × | TEMP. ABANDONED | □ | SECONDARY | □ | TOWNSHIP LINES |
| • | TEST WELL | □ | TERMINATED | | |
| Δ | WATER INJECTION | | | | |
| + | WATER SUPPLY | | | | |
| + | WATER DISPOSAL | | | | |



PREPARED BY: DIANA MASON
DATE: 13-DECEMBER-2002

DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS

Operator Name: Inland Production Company
Name & Number: Canvas Back #15-22-8-17
API Number: 43-013-32240
Location: 1/4,1/4 SW/SE Sec. 22 T. 08S R. 17E

Geology/Ground Water:

Inland has proposed setting 300' of surface casing at this location. The depth to the base of the moderately saline ground water is estimated to be at around 200'. A search of Division of Water Rights records indicates that 6 water wells are located within a 10,000 foot radius of the center of Section 22 . Of these wells 5 are listed as being used for domestic and stock watering. No depths are listed for these wells. The proposed surface casing should extend below the base of the moderately saline water. The other well is a deep water supply well for Inland. The surface formation at this location is the Uinta Formation. The Uinta Formation is made up of interbedded sandstones and shales. The Sandstones are of a discontinuous nature and probably don't represent a significant aquifer. The existing casing should adequately protect any useable ground water.

Reviewer: Brad Hill
Date: 04/10/2001

Surface:

An onsite investigation of the surface area was done on 04/04/01 with Brad Mecham to address and observe any issues regarding any particular needs this well site and access road might have. Mr. Brad Nelson (the landowner of record) was invited by DOGM staff to attend the onsite meeting but declined. The access road proposed by Inland runs adjacent to and immediately south of an irrigated alfalfa field. A dry drainage is present at west end of location with tamarisk and wetland vegetation. However, Inland believes all the water is presently moving east and remaining in field when irrigated. Inland shall berm the location and install any diversion necessary if irrigation waters cause erosion of access road or location. Furthermore, this location is outside the window of tolerance (by 50') for state spacing orders. Inland Representative says this well site was moved north to keep the rig's substructure in cut rather than fill, which appears justified on the cut sheet.

Reviewer: Dennis L. Ingram
Date: April 10, 2001

Conditions of Approval/Application for Permit to Drill:

1. The operator shall properly install and maintain a 12 mil or thicker synthetic liner in reserve pit to prevent seepage of drilling fluids into shallow ground water.

ON-SITE PREDRILL EVALUATION

Division of Oil, Gas and Mining

OPERATOR: Inland Production Company
WELL NAME & NUMBER: Canvas Back #15-22-8-16
API NUMBER: 43-013-32240
LEASE: FEE FIELD/UNIT: MONUMENT BUTTE/CANVASBACK
LOCATION: 1/4, 1/4 SW/SE Sec: 22 TWP: 08S RNG: 17E 2056' FEL 910' FSL
GPS COORD (UTM): 12 586047E; 4439199N
SURFACE OWNER: Brad Nelson

PARTICIPANTS

Dennis L. Ingram (DOGM); Brad Mecham (Inland Production Company)

REGIONAL/LOCAL SETTING & TOPOGRAPHY

Proposed immediately south of irrigated alfalfa field on southern edge of tabletop landscape, overlooking the head (or beginnings) of Big Wash Drainage system in Pleasant Valley approximately 10.3 miles south of Myton, Utah

SURFACE USE PLAN

CURRENT SURFACE USE: Undeveloped rangeland used for wildlife and grazing

PROPOSED SURFACE DISTURBANCE: Proposed 924' of new access road in from east with a location measuring 300'x 170'

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: See attached map from GIS data base

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: All production Facilities shall remain on location; gas residue and sales line of flex pipe on surface along right-of-way.

SOURCE OF CONSTRUCTION MATERIAL: Native cut and fill, borrowed

ANCILLARY FACILITIES: None

WASTE MANAGEMENT PLAN:

Attached and submitted to DOGM with Application to Drill.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: None

FLORA/FAUNA: Shadscale, native grass, salt grass, rabbit brush, sage brush, tamarisk, prickly-pear cactus; mule deer, elk, mountain lion, coyote, raccoon, fox, small birds, birds of prey and other small animals typical of the region.

SOIL TYPE AND CHARACTERISTICS: Tan to light brown fine grained sandy Loam with some clays present.

SURFACE FORMATION & CHARACTERISTICS: Uinta Formation of the Upper Eocene Age

EROSION/SEDIMENTATION/STABILITY: Minor erosion, some sedimentation,

no stability problems anticipated

PALEONTOLOGICAL POTENTIAL: None observed during onsite meeting

RESERVE PIT

CHARACTERISTICS: Located on north side in cut and parallel with prevailing winds measuring 40'x 90'x 8' deep.

LINER REQUIREMENTS (Site Ranking Form attached): 35 points

SURFACE RESTORATION/RECLAMATION PLAN

According to Landowner agreement

SURFACE AGREEMENT: Yes

CULTURAL RESOURCES/ARCHAEOLOGY: Inland submitted Arch report Waiver from Mr. Brad Nelson, releasing them from survey obligations

OTHER OBSERVATIONS/COMMENTS

Access road enters location from the east and immediately south of irrigated alfalfa field with narrow draw which extend south into Big Wash Drainage System. Water from irrigated field appears to drain east and adjacent to location. Old draws are dry but did at one time have water seeps down them, according to surface vegetation. Location was moved north out of window of tolerance to find a stable pad for drill rig, according to operator representative. The cut and fill sheet, plus visual inspection, seems to support their request to move said week because of that reason.

ATTACHMENTS:

Photos of surface area before disturbance

Dennis L. Ingram
DOGM REPRESENTATIVE

04/04/01 10:35 AM
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>10</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	15	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>Unknown</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	15	
TDS >10000 or Oil Base	20	
Mud Fluid containing high levels of hazardous constituents		<u>15</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>Unknown</u>
Final Score (Level II Sensitivity)		<u>35 points</u>

ck 15-22-8-17















UTAH DIVISION OF WATER RIGHTS
WATER RIGHT POINT OF DIVERSION PLOT CREATED TUE, APR 10, 2001, 3:30 PM
PLOT SHOWS LOCATION OF 6 POINTS OF DIVERSION

PLOT OF AN AREA WITH A RADIUS OF 10000 FEET FROM A POINT
FEET, FEET OF THE CT CORNER,
SECTION 22 TOWNSHIP 8S RANGE 17E SL BASE AND MERIDIAN

PLOT SCALE IS APPROXIMATELY 1 INCH = 4000 FEET





UTAH DIVISION OF WATER RIGHTS
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	CFS	QUANTITY AND/OR	AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER	DEPTH	YEAR LOG	NORTH	POINT OF DIVERSION EAST	DESCRIPTION CNR	SEC	TWN	RNG	B&M	
0	47 1501	.0150		.00	Underground Water Well			S	50	W	50	N4 21	8S	17E	SL
		WATER USE(S): IRRIGATION DOMESTIC STOCKWATERING										PRIORITY DATE: 09/05/196			
		Abegglen, Clark and Arva										Myton			
1	47 1346	.0150		.00	Underground Water Well			S	1730	W	100	NE 21	8S	17E	SL
		WATER USE(S): DOMESTIC										PRIORITY DATE: 03/18/195			
		Roberts, Louis Clark										Myton			
2	47 1341	.0150		.00	Underground Water Well			N	1350	W	2230	SE 21	4S	1W	US
		WATER USE(S): DOMESTIC STOCKWATERING										PRIORITY DATE: 10/18/195			
		Roberts, Dean D.					68 East 400 North					Farmington			
3	47 1335	.0150		.00	Underground Water Well			S	2050	E	470	W4 21	4S	1W	US
		WATER USE(S): DOMESTIC										PRIORITY DATE: 08/07/194			
		Roberts, Howard D.										Myton			
4	47 1805	.0460		.00	8	0 - 4990		N	515	E	517	SW 21	8S	17E	SL

WATER USE(S): OTHER
Inland Production Company

410 17th Street, Suite 700

PRIORITY DATE: 05/31/199
Denver

5 47 1336 .0150 .00 Underground Water Well

N 80 E 340 SW 22 4S 1W US

WATER USE(S): DOMESTIC
Jorgensen, Andrew M.

PRIORITY DATE: 03/10/194
Myton

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:
3160
(UT-922)

March 30, 2001

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2001 Plan of Development Canvasback Unit,
Duchesne County, Utah.

Pursuant to email between Lisha Cordova, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management. The following wells are planned for calendar year 2001 within the Canvasback Unit, Duchesne County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ Grrv)		
43-013-32238	13A-22-8-17	Sec. 22, T8S, R17E 0565 FSL 0822 FWL
43-013-32239	14-22-8-17	Sec. 22, T8S, R17E 0664 FSL 2067 FWL
43-013-32240	15-22-8-17	Sec. 22, T8S, R17E 0910 FSL 2056 FEL
43-013-32241	16-22-8-17	Sec. 22, T8S, R17E 0624 FSL 0465 FEL

This office has no has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Canvasback Unit
Division of Oil Gas and Mining
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:3-30-1

**Jon D. Holst &
Associates, LLC**

2507 Flintridge Place
Ft. Collins, CO 80521
Phone: 970-481-1202
Fax: 707-313-3778
jondholst@yahoo.com

May 1, 2001

State of Utah
Department of Natural Resources
Division of Oil, Gas and Mining
ATTN: Lisha Cordova
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Exceptional Spacing for Canvasback 15-22-8-17 Well Location

Dear Lisha:

Please note that the 15-22-8-17 well location will require exceptional spacing due to topographic constraints. The proposed well location has been moved further north into the existing Canvasback Unit and will be 910 feet from the nearest lease or unit boundary, therefore, it will not require written consent from adjacent lease or unit interest owners as required under Rule 649-3-3.

If you have any additional questions or require additional information regarding the location of this proposed well, please contact me at (970) 481-1202.

Respectfully,


Jon D. Holst

REC-111
MAY 1 2001
DIVISION OF OIL, GAS & MINING
SALT LAKE CITY, UT



INLAND PRODUCTION COMPANY

410 17th Street, Suite 700

Denver, CO 80202

303-893-0102

Fax #303-893-0103

Date: December 12, 2002

To: Lisha Cordova
State of Utah, Division of Oil, Gas & Mining
Phone: 801-538-5296
Fax: 801-359-3940

From: Jeff Fandrich
Phone: 303-382-4422
Fax: 303-893-0103

Pages (incl. cover sheet): Three (3)

Subject: APDs for the Canvasback 14-22, 15-22, 16-22, 13-23, and 14-23 wells

Attached are two Memorandums of Surface Agreements covering the captioned APDs which have been previously submitted to your office. We have submitted the originals for recording in the respective counties. Please notify us if there is anything further needed to approve the APDs.

Thanks for your assistance. Happy Holidays!

If you do not receive all pages or there is a problem with this transmission, please call sender. This message and all attachments may contain privileged and/or confidential information. If you are not the intended recipient(s), or the employee or agent responsible for delivery of this message and attachments to the intended recipient(s), you are hereby notified that any dissemination, distribution or copying of this message is strictly prohibited. If you have received this message in error, please immediately notify the sender and return all copies via regular mail to the above address.

cc: Roosevelt - Mandie Crozier
Jon Holst

RECEIVED

DEC 12 2002

DIV. OF OIL, GAS & MINING



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210
PO Box 145801
Salt Lake City, Utah 84114-5801
(801) 538-5340 telephone
(801) 359-3940 fax
(801) 538-7223 TTY
www.nr.utah.gov

Michael O. Leavitt
Governor

Robert L. Morgan
Executive Director

Lowell P. Braxton
Division Director

December 16, 2002

Inland Production Company
410 - 17th Street, Suite 700
Denver, UT 80202

Re: Canvasback 15-22-8-17 Well, 910' FSL, 2056' FEL, SW SE, Sec. 22, T. 8 South,
R. 17 East, Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-32240.

Sincerely,

John R. Baza
Associate Director

pb

Enclosures

cc: Duchesne County Assessor
Bureau of Land Management, Vernal District Office

Operator: Inland Production Company
Well Name & Number Canvasback 15-22-8-17
API Number: 43-013-32240
Lease: UTU-77233

Location: SW SE Sec. 22 T. 8 South R. 17 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

016

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK DRILL ☒ DEEPEN ☐

1b. TYPE OF WELL

OIL WELL ☒ GAS WELL ☐ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☒

2. NAME OF OPERATOR

Inland Production Company

3. ADDRESS OF OPERATOR

410 - 17th Street, Suite 700, Denver, CO 80202

Phone: (303) 893-0102

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At Surface SW/SE 2056' FEL 910' FSL

At proposed Prod. Zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately 11.66 miles southeast of Myton, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also)

Approx. 910' f/lse line & 910' f/unit line

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT.

Approx. 1403'

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5168' GR

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH	QUANTITY OF CEMENT
Refer to Monument Butte Field SOP's Drilling Program/Casing Design				

Inland Production Company proposes to drill this well in accordance with the attached exhibits.

The Conditions of Approval are also attached.

5. LEASE DESIGNATION AND SERIAL NO.

UTU-77233

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

Canvasback Unit

8. FARM OR LEASE NAME WELL NO

Canvasback

9. API WELL NO.

15-22-8-17

10. FIELD AND POOL OR WILDCAT

Monument Butte

11. SEC., T., R., M., OR BLK.

AND SURVEY OR AREA

SW/SE

Sec. 22, T8S, R17E

12. County

Duchesne

13. STATE

UT

16. NO. OF ACRES IN LEASE

1202.78

17. NO. OF ACRES ASSIGNED TO THIS WELL

40

19. PROPOSED DEPTH

6500'

20. ROTARY OR CABLE TOOLS

Rotary

22. APPROX. DATE WORK WILL START*

3rd Quarter 2001

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM : If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED [Signature] TITLE Operations Manager DATE 03/22/2001

(This space for Federal or State office use)

NOTICE OF APPROVAL

PERMIT NO.

APPROVAL DATE

CONDITIONS OF APPROVAL ATTACHED

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

[Signature] Assistant Field Manager
Mineral Resources

DATE

12/24/2002

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

MAR 26 2001

RECEIVED

JAN 03 2003

DIV. OF OIL, GAS & MINING

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Inland Production Company

Well Name & Number: Canvasback 15-22-8-17

API Number: 43-013-32240

Lease Number: U-77233

Location: SWSE Sec. 22 T.8S R. 17E

Agreement: Canvasback Unit

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

1. Other Information

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874 (CELL)
Petroleum Engineer

Kirk Fleetwood (435) 828-7875 (CELL)
Petroleum Engineer

BLM FAX Machine (435) 781-4410

SURFACE USE PROGRAM
Conditions of Approval (COA)
Inland Production Company - Well No. 15-22-9-17 & 16-22-9-17

Plans For Reclamation of Location:

All seeding for reclamation operations at this location shall use the following seed mixture:

shadscale	Atriplex confertifolia	3 lbs/acre
Gardners salt bush	Atriplex gardneri	3 lbs/acre
galleta grass	Hilaria jamesii	3 lbs/acre
mat salt bush	Atriplex corrugata	3 lbs/acre

If the seed mixture is to be aerially broadcasted, the pounds per acre shall be doubled. All seed poundages are in Pure Live Seed.

Immediately after construction the stockpiled top soil will be seeded and the seed worked into the soil by "walking" the pile with caterpillar tracks.

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: INLAND PRODUCTION COMPANYWell Name: CANVASBACK 15-22-8-17Api No: 43-013-32240 Lease Type: FED-MIN, FEE-SURFSection 22 Township 08S Range 17E County DUCHESNEDrilling Contractor STUBBS DRILLING RIG# 111**SPUDDED:**Date 02/21/03Time 6:00 AMHow DRY**Drilling will commence:** _____Reported by PAT WISENERTelephone # 1-435-823-7468Date 02/26/2003 Signed: CHD

INLAND PRODUCTION COMPANY - CASING & CEMENT REPORT

009

8 5/8 CASING SET AT 311.23

LAST CASING 8 5/8" SET AT 311.23'
 DATUM 12' KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 305 LOGGER _____
 HOLE SIZE 12 1/4

OPERATOR Inland Production Company
 WELL Canvasback 14-22-8-17
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # Stubbs # 111

LOG OF CASING STRING:								
PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH	
		40.0 sh jt' shjt						
		WHI - 92 csg head			8rd	A	0.95	
7	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	299.38	
		GUIDE shoe			8rd	A	0.9	
CASING INVENTORY BAL.			FEET	JTS	TOTAL LENGTH OF STRING			301.23
TOTAL LENGTH OF STRING			301.23	7	LESS CUT OFF PIECE			2
LESS NON CSG. ITEMS			1.85		PLUS DATUM TO T/CUT OFF CSG			12
PLUS FULL JTS. LEFT OUT			0		CASING SET DEPTH			311.23
TOTAL			291.99	7	RECEIVED FEB 26 2003 DIV. OF OIL, GAS & MINING			
TOTAL CSG. DEL. (W/O THRDS)			291.99	7				
TIMING			1ST STAGE					
BEGIN RUN CSG.			SPUD	02/19/2003				
CSG. IN HOLE				10:30am	} COMPARE GOOD CIRC THRU JOB <u>Yes</u> Bbls CMT CIRC TO SURFACE <u>4</u> RECIPROCATED PIPE FOR _____ THRU _____ FT STROKE DID BACK PRES. VALVE HOLD ? <u>N/A</u> BUMPED PLUG TO _____ 200 PSI			
BEGIN CIRC								
BEGIN PUMP CMT								
BEGIN DSPL. CMT								
PLUG DOWN			Cemented	02/22/2003				
CEMENT USED		CEMENT COMPANY- B. J.						
STAGE	# SX	CEMENT TYPE & ADDITIVES						
1	150	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield						
CENTRALIZER & SCRATCHER PLACEMENT				SHOW MAKE & SPACING				
Centralizers - Middle first, top second & third for 3								

COMPANY REPRESENTATIVE Pat Wisener

DATE _____

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

010

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

2056' FEL & 910' FSL SW/SE Sec 22. TWN 8S. R17E

5. Lease Designation and Serial No.

UTU-77233

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

Canvasback

8. Well Name and No.

15-22-8-17

9. API Well No.

43-013-32240

10. Field and Pool, or Exploratory Area

11. County or Parish, State

Duchesne, Utah

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other **Spud Report**

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

On 2-21-03. MIRU Stubbs # 111. Drill 305' of 12 1/4" hole with air mist. TIH w/ 7 Jt's 85/8" J-55 24# csgn. Set @ 310.08'/KB On 3/06/03 cement with 250 sks of Class "G" w/ 2% CaCL2 + 1/4# sk Cello-Flake Mixed @ 15.8 ppg > 1.17 cf/sk yeild. 10 bbls cement returned to surface. WOC.

RECEIVED

MAR 12 2003

DIVISION OF MINING

14. I hereby certify that the foregoing is true and correct

Signed

Pat Wisener
Pat Wisener

Title

Drilling Foreman

Date

03/07/2003

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

CC: Utah DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

INLAND PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 310.08

LAST CASING 8 5/8" SET AT 310.08'
 DATUM 12' KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 305 LOGGER _____
 HOLE SIZE 12 1/4

OPERATOR Inland Production Company
 WELL Canvasback 15-22-8-17
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # Stubbs # 111

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		42.77 sh jt' shjt					
		WHI - 92 csg head			8rd	A	0.95
7	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	302.23
		GUIDE shoe			8rd	A	0.9

CASING INVENTORY BAL.	FEET	JTS	TOTAL LENGTH OF STRING	304.08
TOTAL LENGTH OF STRING	304.08	7	LESS CUT OFF PIECE	6
LESS NON CSG. ITEMS	1.85		PLUS DATUM TO T/CUT OFF CSG	12
PLUS FULL JTS. LEFT OUT	0		CASING SET DEPTH	310.08
TOTAL	291.99	7	} COMPARE	
TOTAL CSG. DEL. (W/O THRDS)	302.23	7		
TIMING	1ST STAGE			
BEGIN RUN CSG.	SPUD	02/21/2003	GOOD CIRC THRU JOB	Yes
CSG. IN HOLE		6:30am	Bbls CMT CIRC TO SURFACE	10
BEGIN CIRC			RECIPROCATED PIPE FOR	THRU FT STROKE
BEGIN PUMP CMT			DID BACK PRES. VALVE HOLD ?	N/A
BEGIN DSPL. CMT			BUMPED PLUG TO	200 PSI
PLUG DOWN	Cemented	03/06/2003		

CEMENT USED	CEMENT COMPANY- B. J.		
STAGE	# SX	CEMENT TYPE & ADDITIVES	
1	250	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield	

CENTRALIZER & SCRATCHER PLACEMENT	SHOW MAKE & SPACING
Centralizers - Middle first, top second & third for 3	RECEIVED
	MAR 12 2003

DIV. OF OIL, GAS & MINING

COMPANY REPRESENTATIVE Pat Wisener

DATE 03/07/2003

011

P. 02

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR INLAND PRODUCTION COMPANY
ADDRESS RT. 3 BOX 3833
JOYCE, UT 84052

OPERATOR ACCT. NO. NS160

FAX NO. 435 846 3031

INLAND PRODUCTION CO

MAR-14-03 FRI 10:39 AM

ACTION CODE	CURRENT ENTRY NO	NEW ENTRY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CG	SC	TP	RG	COUNTY		
A	99999	12299	43-013-32240	Canvasback #15-22-8-17	SW/8E	22	8S	17E	Duchesne	February 21, 2003	02/21/03

WELL 1 COMMENTS

ACTION CODE	CURRENT ENTRY NO	NEW ENTRY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CG	SC	TP	RG	COUNTY		
	99999	12299	43-013-32341	Canvasback #12-23-8-17	NW/8W	23	8S	17E	Duchesne	March 5, 2003	03/05/03

WELL 2 COMMENTS

ACTION CODE	CURRENT ENTRY NO	NEW ENTRY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CG	SC	TP	RG	COUNTY		

WELL 3 COMMENTS

ACTION CODE	CURRENT ENTRY NO	NEW ENTRY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CG	SC	TP	RG	COUNTY		

WELL 4 COMMENTS

ACTION CODE	CURRENT ENTRY NO	NEW ENTRY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					CG	SC	TP	RG	COUNTY		

WELL 5 COMMENTS

ACTION CODES (See INSTRUCTIONS on back of form)


- A. Extension from existing formation well (single well)
- B. New well - extending from existing well
- C. Extension from existing well to new formation
- D. Extension from existing well to new formation
- E. Other (Specify in comments section)

NOTE: Use DISPOSITION section to indicate each ACTION CODE was entered

RECEIVED

MAR 14 2003

DIV. OF OIL, GAS & MINING


Signature
Keesha S. Jones
Production Clerk
March 14, 2003
Date

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

012

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

2056' FEL & 910' FSL SW/SE Sec 22. T2N 8S. R17E

5. Lease Designation and Serial No.

UTU-77233

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

Canvasback

8. Well Name and No.

15-22-8-17

9. API Well No.

43-013-32240

10. Field and Pool, or Exploratory Area

11. County or Parish, State

Duchesne, Utah

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other **Weekly Status Report**

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Weekly Status report for the period of 3-16-03 thru 3-24-03.

RECEIVED

MAR 26 2003

DIV. OF OIL, GAS & MINING

On 3-19-03 MIRU Eagle # 1. Set equipment. Pressure test Bop's, Kelly, TIW to 2,000 psi. Test 85/8" csgn to 1,500 psi. Vernal BLM office was notified of test. PU & MU BHA and tag cement @ 260'. Drill out cement and shoe. Con't to drill 77/8" hole with fresh water to a depth of 6318'. Lay down drill string. Open hole log. PU & MU Guide shoe, 1 jt 5 1/2" csg, Float collar & 146jt's J-55 15.5 # 5 1/2" csgn. Set @ 6299'/KB. Cement with 400* sks. 50/50 POZ w/ 3% KCL, 1/4#sk Cello-Flake, 2% Gel, .3%SMS, .05#sk Static free, Mixed @ 14.4PPG >1.24 YLD. Then 310* sks Prem Litell w/ 3% KCL, 3#/sk Kolseal, 8% Gel, .5SMS, 3#sk CSE, mixed @ 11.0PPG >3.43. Good returns thru job with 45 bbls of 50 bbls dye water to pit. Set slips with 76,000# tension. Nipple down BOP's. Release rig @ 5:30 pm on 3-24-03

14. I hereby certify that the foregoing is true and correct

Signed

Pat Wisener

Title

Drilling Foreman

Date

03/24/2003

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

CC: Utah DOGM

INLAND PRODUCTION COMPANY - CASING & CEMENT REPORT

5 1/2" CASING SET AT 6299.92

Flt cllr @ 6281'

LAST CASING 8 5/8" SET AT 310.08'

OPERATOR Inland Production Company

DATUM 12' KB

WELL Canvasback 15-22-8-17

DATUM TO CUT OFF CASING 12'

FIELD/PROSPECT Monument Butte

DATUM TO BRADENHEAD FLANGE

CONTRACTOR & RIG # Eagle # 1

TD DRILLER 6318' LOGGER 6300'

HOLE SIZE 7 7/8"

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		Landing Jt					14
		38' @ 4004'					
146	5 1/2"	ETC LT & C casing	15.5#	J-55	8rd	A	6269.67
		Float collar					0.6
1	5 1/2"	ETC LT&C csg	15.5#	J-55	8rd	A	17
		GUIDE shoe			8rd	A	0.65
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING			6301.92
TOTAL LENGTH OF STRING		6301.92	147	LESS CUT OFF PIECE			14
LESS NON CSG. ITEMS		15.25		PLUS DATUM TO T/CUT OFF CSG			12
PLUS FULL JTS. LEFT OUT		36.8	1	CASING SET DEPTH			6299.92
TOTAL		6323.47	148	} COMPARE			
TOTAL CSG. DEL. (W/O THRDS)		6323.47	148				
TIMING		1ST STAGE	2nd STAGE				
BEGIN RUN CSG.		8:30am		GOOD CIRC THRU JOB <u>YES</u>			
CSG. IN HOLE		11:30am		Bbls CMT CIRC TO SURFACE <u>40 of 50 bbls dye water</u>			
BEGIN CIRC		11:45am	11:47am	RECIPROCATED PIPE FOR <u>THRUSTROKE</u>			
BEGIN PUMP CMT		11:55am	12:23pm	DID BACK PRES. VALVE HOLD ? <u>Yes</u>			
BEGIN DSPL. CMT		12:45pm		BUMPED PLUG TO <u>1700</u> PSI			
PLUG DOWN			1:10pm				

CEMENT USED		CEMENT COMPANY- B. J.	
STAGE	# SX	CEMENT TYPE & ADDITIVES	
1	310	Premlite II w/ 10% gel + 3 % KCL, 3#s /sk CSE + 2# sk/kolseal + 1/4#s/sk Cello Flake	
		mixed @ 11.0 ppg W / 3.43 cf/sk yield	
2	400	50/50 poz W/ 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM mixed @ 14.4 ppg W/ 1.24 YLD	
CENTRALIZER & SCRATCHER PLACEMENT		SHOW MAKE & SPACING	RECEIVED MAR 26 2003 DIV. OF OIL, GAS & MINING
Centralizers - Middle first, top second & third. Then every third collar for a total of 20.			

COMPANY REPRESENTATIVE Pat Wisener

DATE 03/24/2003

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

013

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

FORM APPROVED

Budget Bureau No. 1004-0135

Expires: March 31, 1993

5. Lease Designation and Serial No.

UTU-77233

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

CANVASBACK

8. Well Name and No.

CANVASBACK 15-22-8-17

9. API Well No.

43-013-32240

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

DUCHESNE COUNTY, UT

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

910 FSL 2056 FEL SW/SE Section 22, T8S R17E

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing

☒ **Weekly status report**

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Status report for time period 4/14/03 - 4/24/03

Subject well had completion procedures initiated in the Green River formation on 4/14/03 without use of a service rig over the well. A cement bond log was run and a total of three Green River intervals were perforated and hydraulically fracture treated w/ 20/40 mesh sand. Stage #1: CP3 sds (6216-6227'), (6205-6214') and CP2 sds (6158 6171') were perforated. All 4 JSPF. A service rig was then moved on well on 4/17/03. The remainder of stage #1 was perforated: CP4 sds (6285-6295'). All 4 JSPF. The CP2, 3 and 4 interval was then hydraulically fracture treated with 20/40 mesh sand. Stage #2: CP1 sds (6094-6105'), (6084-6090') and CP.5 sds (6054-6061') were perforated and hydraulically fracture treated with 20/40 mesh sand. All 4 JSPF. Stage #3: LODC sds (5773-5777') and (5755-5759') were perforated and hydraulically fracture treated with 20/40 mesh sand. All 4 JSPF. Composite flow-through frac plugs were used between stages. Fracs were flowed back through chokes. Bridge plugs were drilled out. Zones were swab tested for sand cleanup. Sand was cleaned out to TD @ 6318'. A BHA and production tbg string were run in and anchored in well. End of tubing string @ 6221'. A repaired 1 1/2" bore rod pump was run in well on sucker rods. Well was placed on production via rod pump on 4/24/03.

14. I hereby certify that the foregoing is true and correct

Signed

Martha Hall

Title

Office Manager

Date

4/25/2003

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

APR 28 2003



May 27, 2003

State of Utah, Division of Oil, Gas and Mining
Attn: Ms. Carol Daniels
P.O. Box 145801
Salt Lake City, Utah 84144-5801

Attn: Ms. Carol Daniels

Canvasback 15-22-8-17 (43-013-32240)
Duchesne County, UT

Dear Ms. Carol Daniels

Enclosed is a Well Completion or Recompletion Report and Log form (Form 3160-4). We are no longer sending Log copies since Dave Jull of Phoenix Surveys is already doing so.

If you should have any questions, please contact me at (303) 382-4449.

Sincerely,

Brian Harris
Engineering Tech

Enclosures

cc: Bureau of Land Management
Vernal District Office, Division of Minerals
Attn: Edwin I. Forsman
170 South 500 East
Vernal, Utah 84078

Well File – Denver
Well File – Roosevelt
Patsy Barreau/Denver
Bob Jewett/Denver

RECEIVED
MAY 29 2003
DIV. OF OIL, GAS & MINING

SUBMIT IN DUPLICATE*

(See other instructions on reverse side)

FORM APPROVED

OMB NO. 1004-0137

Expires: February 28, 1995

014

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WORK

OIL WELL ☒GAS WELL ☐DRY ☐

Other _____

1b. TYPE OF WELL

NEW WELL ☒WORK OVER ☐DEEPEN ☐PLUG BACK ☐DIFF RESVR. ☐

Other _____

2. NAME OF OPERATOR

INLAND RESOURCES INC.

3. ADDRESS AND TELEPHONE NO.

410 17th St. Suite 700 Denver, CO 80202

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.)*

At Surface

910' FSL & 2056' FEL (SWSW) Sec. 22, Twp 8S, Rng 17E

At top prod. Interval reported below

At total depth

14. API NO.

43-013-32240

DATE ISSUED

12/24/02

15. DATE SPUDDED

2/21/03

16. DATE T.D. REACHED

3/23/03

17. DATE COMPL. (Ready to prod.)*

4/24/03

18. ELEVATIONS (DF, RKB, RT, GR, ETC.)*

GI 5168'

12. COUNTY OR PARISH

Duchesne

13. STATE

UT

20. TOTAL DEPTH, MD & TVD

6318'

21. PLUG BACK T.D., MD & TVD

6299'

22. IF MULTIPLE COMPL., HOW MANY*

GI 5168'

KB 5180'

19. ELEV. CASINGHEAD

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)*

Green River 5755'-6295'

25. WAS DIRECTIONAL SURVEY MADE

No

26. TYPE ELECTRIC AND OTHER LOGS RUN

Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log

27. WAS WELL CORED

No

23. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
8-5/8" - J-55	24#	310'	12-1/4"	To surface with 250 sx Class "G" cmt	
5-1/2" - J-55	15.5#	6299'	7-7/8"	310 sx Premlite II and 400 sx 50/50 Poz	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					2-7/8"	EOT @ 6220'	TA @ 6119'

31. PERFORATION RECORD (Interval, size and number)

INTERVAL	SIZE	SPF/NUMBER	DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
(CP2,3,4) 6285-95', 6216-27', 6205'-14', 6158-71'	.038"	4/172	6158'-6295'	Frac w/ 98,671# 20/40 sand in 424 bbls fluid
(CP.5,1) 6094-6105', 6084-90', 6054-61'	.038"	4/96	6054'-6105'	Frac w/ 78,834# 20/40 sand in 343 bbls fluid
(LODC) 5773-77', 5755-59'	.038"	4/32	5755'-5777'	Frac w/ 19,757# 20/40 sand in 91 bbls fluid

33.*

PRODUCTION

DATE FIRST PRODUCTION 4/24/03		PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) 2-1/2" x 1-1/2" x 15' RHAC Pump					WELL STATUS (Producing or shut-in) PRODUCING	
DATE OF TEST 10 day ave	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD ---->	OIL--BBL. 63	GAS--MCF. 63	WATER--BBL. 20		GAS-OIL RATIO 1000
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE ---->	OIL-BBL.	GAS--MCF.	WATER--BBL.		OIL GRAVITY (API GRAV.)	

RECEIVE

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold & Used for Fuel

TEST WITNESSED BY

MAY 29 2003

35. LIST OF ATTACHMENTS

DIV. OF OIL, GAS & MINING

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

Brian Harris

TITLE

Engineering Technician

DATE

5/27/2003

BDH

*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
			Well Name Canvasback 15-22-8-17	Garden Gulch Mkr	4390'	
				Garden Gulch 2	4506'	
				Point 3 Mkr	4783'	
				X Mkr	5018'	
				Y-Mkr	5052'	
				Douglas Creek Mkr	5141'	
				BiCarbonate Mkr	5454'	
				B Limestone Mkr	5594'	
				Castle Peak	6034'	
				Basal Carbonate		
				Total Depth (LOGGERS	6318'	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

015

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

5. Lease Designation and Serial No.

UTU-77233

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

CANVASBACK

8. Well Name and No.

CANVASBACK 15-22-8-17

9. API Well No.

43-013-32240

10. Field and Pool, or Exploratory Area

MONUMENT BUTTE

11. County or Parish, State

DUCHESNE COUNTY, UT

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

INLAND PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

910 FSL 2056 FEL SW/SE Section 22, T8S R17E

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☐ Other
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☒ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Formation water is produced to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Inland's secondary recovery project.

Water not meeting quality criteria, is disposed at Inland's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

14. I hereby certify that the foregoing is true and correct

Signed

Mandie Crozier
Mandie Crozier

Title

Regulatory Specialist

Date

11/14/2003

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Conditions of approval, if any:

CC: Utah DOGM

RECEIVED

NOV 17 2003

Date

DIV. OF OIL, GAS & MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>



IN REPLY REFER TO:
3106
(UT-924)

September 16, 2004

Memorandum

To: Vernal Field Office
From: Acting Chief, Branch of Fluid Minerals
Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard
Acting Chief, Branch of
Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare

UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		



Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas
SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐
(highlight changes)

001

APPLICATION FOR PERMIT TO DRILL				5. MINERAL LEASE NO: ML-22347-A	6. SURFACE: State
1A. TYPE OF WORK: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>				7. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
B. TYPE OF WELL: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/>				8. UNIT or CA AGREEMENT NAME:	
2. NAME OF OPERATOR: WESTPORT OIL & GAS COMPANY L.P.				9. WELL NAME and NUMBER: LOVE 1121-16H	
3. ADDRESS OF OPERATOR: 1368 S. 1200 E. CITY VERNAL STATE UT ZIP 84078				10. FIELD AND POOL, OR WILDCAT: UNDESIGNATED	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 2539'FNL & 460'FEL AT PROPOSED PRODUCINGZONE:				11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SENE 16 11S 21E	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 27.1 MILES SOUTHEAST OF OURAY, UTAH				12. COUNTY: UINTAH	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 460'		16. NUMBER OF ACRES IN LEASE: 1275.39		17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 40	
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) REFER TO TOPO C		19. PROPOSED DEPTH: 8,800		20. BOND DESCRIPTION: RLB0005238	
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.): 5518'GL		22. APPROXIMATE DATE WORK WILL START:		23. ESTIMATED DURATION:	

24. PROPOSED CASING AND CEMENTING PROGRAM					
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT			SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT
12 1/4	9 5/8	H-40	32.3#	1,900	265 SX
7 7/8	4 1/2	I-80	11.6#	8,800	1880 SX

25. ATTACHMENTS	
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES:	
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER	<input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER

NAME (PLEASE PRINT) SHEILA WPCHEGO TITLE REGULATORY ANALYST
SIGNATURE [Signature] DATE 1/20/2005

(This space for State use only)

API NUMBER ASSIGNED: 43-047-36257

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 03-10-05

(See Instructions on Reverse Side)

RECEIVED

JAN 24 2005

DIV. OF OIL, GAS & MINING


WESTPORT OIL AND GAS COMPANY, L.P.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

BASIS OF ELEVATION

SPOT ELEVATION AT THE SOUTHEAST CORNER OF SECTION 2, T11S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE, QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5584 FEET.




S C A L E
CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE MAP WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.




REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

UTAH ENGINEERING & LAND SURVEYING
 85 SOUTH 200 EAST - VERNAL, UTAH 84078
 (435) 789-1017

SCALE 1" = 1000'		DATE SURVEYED: 11-29-04	DATE DRAWN: 12-16-04
PARTY K.K. F.I. E.C.O.		REFERENCES G.L.O. PLAT	
WEATHER COOL		FILE WESTPORT OIL AND GAS COMPANY, L.P.	



LEGEND:

-  = 90° SYMBOL
 = PROPOSED WELL HEAD.
 = SECTION CORNERS LOCATED.

(AUTONOMOUS NAD 83)
 LATITUDE = 39°51'39.12" (39.860867)
 LONGITUDE = 109°33'52.72" (109.564644)

(AUTONOMOUS NAD 27)
 LATITUDE = 39°51'39.24" (39.860900)
 LONGITUDE = 109°33'50.25" (109.563958)

OPERATOR CHANGE WORKSHEET

017

Change of Operator (Well Sold)

Designation of Agent/Operator

ROUTING

1. GLH

2. CDW

3. FILE

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

9/1/2004

FROM: (Old Operator):
 N5160-Inland Production Company
 Route 3 Box 3630
 Myton, UT 84052
 Phone: 1-(435) 646-3721

TO: (New Operator):
 N2695-Newfield Production Company
 Route 3 Box 3630
 Myton, UT 84052
 Phone: 1-(435) 646-3721

CA No.

Unit:

CANVASBACK (GREEN RIVER)

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
BALCRON FED 12-22Y	22	080S	170E	4301331476	12299	Federal	WI	A
BALCRON MON FED 22-22-8-17Y	22	080S	170E	4301331538	12299	Federal	OW	P
BALCRON MON FED 11-22-8-17Y	22	080S	170E	4301331539	12299	Federal	OW	P
MON FED 13-22-8-17Y	22	080S	170E	4301331583	12299	Federal	OW	S
MON FED 32-22-8-17	22	080S	170E	4301331586	12299	Federal	WI	A
MON FED 31-22-8-17	22	080S	170E	4301331587	12299	Federal	OW	P
MON FED 33-22-8-17	22	080S	170E	4301331588	12299	Federal	OW	P
MON FED 23-22-8-17Y	22	080S	170E	4301331702	12299	Federal	WI	A
PARIETTE DRAW 8-22	22	080S	170E	4301331826	12299	Federal	OW	P
CANVASBACK 13A-22-8-17	22	080S	170E	4301332238	12299	Federal	OW	P
CANVASBACK 14-22-8-17	22	080S	170E	4301332239	12299	Federal	OW	P
CANVASBACK 15-22-8-17	22	080S	170E	4301332240	12299	Federal	OW	P
CANVASBACK 16-22-8-17	22	080S	170E	4301332241	12299	Federal	OW	P
FEDERAL 13-23-8-17	23	080S	170E	4301332340	12299	Federal	OW	P
CANVASBACK 12-23-8-17	23	080S	170E	4301332341	12299	Federal	OW	P
CANVASBACK 4-23-8-17	23	080S	170E	4301332342	12299	Federal	OW	P
CANVASBACK 5-23-8-17	23	080S	170E	4301332343	12299	Federal	OW	P
FEDERAL 14-23-8-17	23	080S	170E	4304734556	12299	Federal	OW	P
CANVASBACK 15-23-8-17	23	080S	170E	4304734557	12299	Federal	D	PA
CANVASBACK 3-23-8-17	23	080S	170E	4304734567	12299	Federal	OW	P

K

K

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/2005

4. Is the new operator registered in the State of Utah: YES Business Number: 755627-0143

5. If NO, the operator was contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 2/28/2005
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number 61BSBDH2919

2. The FORMER operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

OPERATOR CHANGE WORKSHEET

019

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change

Merger

ROUTING

1. GLH
2. CDW
3. FILE

The operator of the well(s) listed below has changed, effective:						9/1/2004		
FROM: (Old Operator): N5160-Inland Production Company Route 3 Box 3630 Myton, UT 84052 Phone: 1-(435) 646-3721				TO: (New Operator): N2695-Newfield Production Company Route 3 Box 3630 Myton, UT 84052 Phone: 1-(435) 646-3721				
CA No.			Unit:		CANVASBACK (GREEN RIVER)			
WELL(S)								
NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
BALCRON FED 12-22Y	22	080S	170E	4301331476	12299	Federal	WI	A
BALCRON MON FED 22-22-8-17Y	22	080S	170E	4301331538	12299	Federal	OW	P
BALCRON MON FED 11-22-8-17Y	22	080S	170E	4301331539	12299	Federal	OW	P
MON FED 13-22-8-17Y	22	080S	170E	4301331583	12299	Federal	OW	S
MON FED 32-22-8-17	22	080S	170E	4301331586	12299	Federal	WI	A
MON FED 31-22-8-17	22	080S	170E	4301331587	12299	Federal	OW	P
MON FED 33-22-8-17	22	080S	170E	4301331588	12299	Federal	OW	P
MON FED 23-22-8-17Y	22	080S	170E	4301331702	12299	Federal	WI	A
PARIETTE DRAW 8-22	22	080S	170E	4301331826	12299	Federal	OW	P
CANVASBACK 13A-22-8-17	22	080S	170E	4301332238	12299	Federal	OW	P
CANVASBACK 14-22-8-17	22	080S	170E	4301332239	12299	Federal	OW	P
CANVASBACK 15-22-8-17	22	080S	170E	4301332240	12299	Federal	OW	P
CANVASBACK 16-22-8-17	22	080S	170E	4301332241	12299	Federal	OW	P
FEDERAL 13-23-8-17	23	080S	170E	4301332340	12299	Federal	OW	P
CANVASBACK 12-23-8-17	23	080S	170E	4301332341	12299	Federal	OW	P
CANVASBACK 4-23-8-17	23	080S	170E	4301332342	12299	Federal	OW	P
CANVASBACK 5-23-8-17	23	080S	170E	4301332343	12299	Federal	OW	P
FEDERAL 14-23-8-17	23	080S	170E	4304734556	12299	Federal	OW	P
CANVASBACK 15-23-8-17	23	080S	170E	4304734557	12299	Federal	D	PA
CANVASBACK 3-23-8-17	23	080S	170E	4304734567	12299	Federal	OW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on:

9/15/2004
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on:

9/15/2004
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on:

2/23/2005
4. Is the new operator registered in the State of Utah:

YES

Business Number:

755627-0143
5. If **NO**, the operator was contacted contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE

6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

- 1. Changes entered in the Oil and Gas Database on: 2/28/2005
- 2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 2/28/2005
- 3. Bond information entered in RBDMS on: 2/28/2005
- 4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
- 5. Injection Projects to new operator in RBDMS on: 2/28/2005
- 6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

- 1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

- 1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

- 1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919
- 2. The **FORMER** operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

- 3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

***Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05**



State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

MARY ANN WRIGHT
Acting Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

March 10, 2005

Westport Oil & Gas Company, LP
1368 South 1200 East
Vernal, UT 84078

Re: Love 1121-16H Well, 2539' FNL, 460' FEL, SE NE, Sec. 16, T. 11 South,
R. 21 East, Uintah County, Utah


Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-36257.

Sincerely,


John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
SITLA

Operator: Westport Oil & Gas Company, LP
Well Name & Number Love 1121-16H
API Number: 43-047-36257
Lease: ML-22347-A

Location: SE NE **Sec.** 16 **T.** 11 South **R.** 21 East

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. **Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

6. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

MAR 11 2005

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Mr. Mike Guinn
Vice President - Operations
Newfield Production Co.
Route 3 - Box 3630
Myton, Utah 84502

RECEIVED
MAR 15 2005
DIV. OF OIL, GAS & MINING

RE: ADDITIONAL WELL TO AREA PERMIT
Canvasback Area Permit: UT20855-00000
Canvasback No. 15-22-8-17
Well ID: 20855-06415
SW SE Sec. 22 - T8S - 17E
Duchesne County, Utah

Dear Mr. Guinn:

The Newfield Production Co. (Newfield) request **to convert** a former Green River Formation oil well, the Canvasback No. 15-22-8-17, to a Garden Gulch-Douglas Creek-Basal Carbonate Members of the Green River Formation enhanced recovery injection well in the Canvasback Area Permit is hereby authorized. The proposed Canvasback No. 15-22-8-17 Class II enhanced recovery injection well is within the exterior boundary of the Canvasback Area Permit UT20855-00000; is within the exterior boundary of the Uintah & Ouray Indian Reservation; and the addition is being made under the authority of 40 CFR § 144.33 (c) and the terms of the Area Permit. Unless specifically mentioned in the enclosed Authorization For An Additional Well, all terms and conditions of the original Area Permit will apply to the conversion, operation, monitoring, and plugging and abandonment of the Canvasback No. 15-22-8-17.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY




Prior to beginning injection, the Environmental Protection Agency (EPA) requires that Newfield submit for review and approval (1) the results of a **Part I (Internal) mechanical integrity test (MIT)**, (2) a **pore pressure** calculation of the injection interval, (3) an **EPA Form No. 7520-12** (Well Rework Record, enclosed).

Part II. Section C. Condition No. 5 (b) (1), (Injection Pressure Limitation), Canvasback Area Permit (UT20855-00000) , cites the method by which the maximum initial allowable injection pressure (MAIP) shall be calculated for each Additional Well to the Canvasback Area Permit. As a result, the MAIP for the Canvasback No. 15-22-8-17 shall not exceed **1755 psig**. The Canvasback Area Permit, Part II. C. 5., provides an opportunity for the permittee to request an increase, or decrease, in the initial maximum surface injection pressure.

Please be aware that Newfield does not have authorization to begin injection into the Canvasback No. 15-22-8-17 until the Prior to Commencing Injection requirements, listed above, have been submitted and evaluated by the EPA, and Newfield has received written authorization to begin injection from the Assistant Regional Administrator, or the Assistant Regional Administrator's authorized representative.

If Newfield has any questions, please call Mr. Dan Jackson at (800) 227-8917 (Ext. 6155), or in the Denver area at (303) 312-6155. Please submit the required pre-authorization to inject data to **ATTENTION: DAN JACKSON**, at the letterhead address, citing **MAIL CODE: 8P-W-GW** very prominently.

Sincerely,



Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

enclosures: Authorization For Conversion of An Additional Well
EPA Form No. 7520-12 (Well Rework Record)
Guidance No. 39: Part I Mechanical Integrity (Internall)
Schematic Diagram: Proposed Conversion

cc w/ enclosures: Maxine Natchees
Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe

Elaine Willie
Environmental Coordinator
Ute Indian Tribe

Chester Mills
Superintendent
Bureau of Indian Affairs
Uintah & Ouray Indian Agency

David Gerbig
Operations Engineer
Newfield Production Company

Gil Hunt
Technical Services Manager
State of Utah - Natural Resources

Kirk Fleetwood
Sr. Petroleum Engineer
Bureau of Land Management
Vernal District



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

**AUTHORIZATION FOR AN ADDITIONAL WELL
TO THE
CANVASBACK AREA PERMIT: UT20855-00000**

The Environmental Protection Agency (EPA) authorizes the inclusion of an additional enhanced recovery injection well to the Canvasback Area Permit No. UT20855-00000, as authorized by 40 CFR § 144.33 (c). The additional well is described as:

WELL NAME: CANVASBACK NO. 15-22-8-17

WELL PERMIT NUMBER: UT20855-06415

SURFACE LOCATION: 910' FSL & 2056' FEL (SW SE)
Sec. 22 - T8S - R17E
Duchesne County, Utah.

This well is subject to all provisions of the original Canvasback Area Permit No. UT20855-00000, and subsequent Modifications, unless specifically detailed below:

UNDERGROUND SOURCE OF DRINKING WATER (USDW): The base of the USDW (Total Dissolved Solids less than 10,000 mg/l) in the Canvasback No.15-22-8-17 occurs within the Uinta Formation **less than 50 feet** from ground level (GL). The source for the location of the base of the USDW is the STATE OF UTAH: PUBLICATION NO. 2. BASE OF MODERATELY SALINE GROUND WATER IN THE UINTA BASIN, UTAH. Surface casing was set at **310 feet** kelly bushing (KB) and cemented to the surface.

Reference: <http://NRWRT1.NR.STATE.UT.US...> Water Rights...Queries...POD: Within the one-quarter (1/4) mile Area-of-Review (AOR) around the Canvasback No. 15-22-8-17 there are no reservoirs, streams, springs or wells.

WATER ANALYSES:

Produced Green River Formation Water: (4-28-04) **58,696 mg/l TDS.**

Source Water: Johnson Water District Reservoir. (3/31/04) **400 mg/l TDS.**

Blended Injectate: (5/04/04) **29,803 mg/l TDS.**



CONFINING ZONE REVIEW: CANVASBACK NO. 15-22-8-17. (4756' - 4200')

The EPA has authorized the gross interval from the top of the Garden Gulch Member to the top of the Wasatch as the enhanced recovery injection interval within the Canvasback Area Permit. Overlying the top of the Garden Gulch Member (4200 feet), in the Canvasback No. 15-22-8-17, are thirty-four (34) feet of Green River Formation black, slightly silty, impervious shale which forms an effective lithologic confining zone.

INJECTION ZONE REVIEW: CANVASBACK NO. 15-22-8-17.

The Canvasback Final Area Permit (Effective August 18, 2000) authorized injection into the Garden Gulch and Douglas Creek Members of the Green River Formation. By Major Permit Modification No. 3 (Effective September 10, 2003) the EPA authorized the gross Green River Formation Garden Gulch-Douglas Creek-Basal Carbonate Members as the enhanced recovery injection interval for the Canvasback Area Permit. This Modification also recognized the **Federal No. 1-26** (NE NW Sec. 26 - T8S - R17E), UIC Permit No. UT20702-04671, as the **TYPE WELL** for identifying the tops of the Garden Gulch Member, the Douglas Creek Member, the Basal Carbonate Member, the top of the Wasatch Formation and the "Confining Zone" overlying the top of the Garden Gulch Member.

The authorized injection zone for the Canvasback No. 15-22-8-17 will be from the Garden Gulch Member (4200 feet) to the top of the Wasatch Formation (Estimated to be 6575 feet).

Lithologically, the gross authorized enhanced recovery injection interval, Garden Gulch to the top of the Wasatch Formation, is fluvial and lacustrine shale, fluvial and lacustrine sandstone, lacustrine marlstone, and limestone. The Uinta and Green River Formations are predominantly non-lacustrine fluvial shale and sandstone on the basin margins, whereas lacustrine deposition predominates in the central basin area for these two formations. The Wasatch Formation is predominantly fluvial, except for increasing minor lacustrine deposition in the central basin area.

WELL CONSTRUCTION REVIEW: CANVASBACK NO. 15-22-8-17.

SURFACE CASING: 8-5/8 inch casing is set at 310 feet in a 12-1/4 inch hole, using 250 sacks of Class "G" cement circulated to the surface. The base of the USDW is less than fifty (50) feet from ground level.

LONGSTRING CASING: 5-1/2 inch casing is set at 6300 feet kelly bushing (KB) in a 7-7/8 inch hole, and cemented with 310 sacks of Premium Lite II mixed and 400 sacks of 50/50 Pozmix.

The operator identifies the top of cement at 400 feet.

The EPA analysis of the CBL/GR identifies 80% cement bond index across the Garden Gulch Member confining zone from 2708 feet to 5958 feet.

An EPA analysis of the Canvasback No. 15-22-8-17 CBL/GR did identify 80% bond index cement bond across the Garden Gulch Member confining zone, pursuant to standards of Region 8 GROUND WATER SECTION GUIDANCE NO. 34: Cement Bond Logging Techniques and Interpretation. Therefore, it **has been determined that the cement in this well provides an effective barrier** to significant upward movement of fluids through vertical channels adjacent to the wellbore, pursuant to 40 CFR 146.8 (a) (2).

PART II. A. CONSTRUCTION REQUIREMENTS FOR ADDITIONAL WELLS

Tubing and Packer:

(Condition 3)

For injection purposes, the **Canvasback No. 15-22-8-17** shall be equipped with 2-7/8 tubing with a packer to be set at a depth no higher than 100 feet above the top perforation.

Formation Testing and Logging

(Condition 6)

- (a) Upon conversion of the **Canvasback No. 15-22-8-17**, the permittee is required to determine the injection zone **fluid pore pressure** (static bottom hole pressure) prior to commencement of enhanced recovery injection operation. The results of this test shall be submitted to the EPA.
- (b) A **Step-Rate Test (SRT)** shall be performed on the **Canvasback No. 15-22-8-17** within three (3) to six (6) months after injection operations are initiated and the results submitted to the EPA. The permittee may contact the EPA prior to conducting the SRT to acquire the most current Guidance for conducting the SRT.

PART II. B.

Corrective Action

As of February 2005, there are four (4) active Green River oil wells within or proximate to the one-quarter (1/4) mile radius around the Canvasback No. 15-22-8-17-8-17. No wells need Corrective Action.

Garden Gulch-Douglas Creek Members Oil Wells:**Canvasback No. 14-22-8-17:****SE SW Sec. 22 -T8S-R17E**

Top Garden Gulch Member:	4183 feet
Garden Gulch Confining Zone:	4119 feet to 4183 feet
Top 80% EPA Cement Bond:	3800 feet - 4100 feet and 4216 feet - 4238 feet
Top Douglas Creek Member:	5168 feet
Total Depth (Driller):	6300 feet in Douglas Creek Member

The 64-foot confining shale (4119 feet to 4183 feet) overlying the top of the Garden Gulch Member (4183 feet) is not protected by 80% bond index cement bond. This lack of confining zone annulus cement may not prevent upward movement of injected fluids through vertical channels adjacent to the well bore. The permittee will be required to inspect the surface of this location for fluid leaks on a weekly basis. **Any observation of surface leakage may be considered as noncompliance with the Canvasback No. 15-22-8-17 Permit.** The Canvasback No. 15-22-8-17 shall suspend operations immediately, and will stay suspended until the noncompliance has been resolved, and renewed injection has been approved in writing by the Director.

Canvasback No. 16-22-8-17 :**SE SE Sec. 22-T8S-R17E**

Top Garden Gulch Member:	4198 feet
Garden Gulch Confining Zone:	4154 feet to 4198 feet
Top 80% EPA Cement Bond:	3884 feet - 4128 feet and 4228 feet - 4362 feet.
Top Douglas Creek Member:	5176 feet
Total Depth (Driller):	6379 feet in Douglas Creek Member.

The 44-foot confining shale (4154 feet to 4198 feet) overlying the top of the Garden Gulch Member (4198 feet) is not protected by 80% bond index cement bond. This lack of confining zone annulus cement may not prevent upward movement of injected fluids through vertical channels adjacent to the well bore. The permittee will be required to inspect the surface of this location for fluid leaks on a weekly basis. **Any observation of surface leakage may be considered as noncompliance with the Canvasback No. 15-22-8-17 Permit.** The Canvasback No. 15-22-8-17 shall suspend operations immediately, and will stay suspended until the noncompliance has been resolved, and renewed injection has been approved in writing by the Director.

Greater Boundary No. 2-27-8-17:**NW NE Sec. 27-T8S-R17E**

Top Garden Gulch Member:	4106 feet
Garden Gulch Confining Zone:	4052 feet to 4106 feet
Top 80% EPA Cement Bond:	4074 feet to 4092 feet
Top Douglas Creek Member:	5098 feet
Total Depth (Driller):	6304 feet in Douglas Creek Member

The 54-foot Confining Zone contains eighteen (18) feet of continuous 80% bond index cement bond. This annulus cement is considered adequate to confine the injectate to the authorized injection interval.

Monument Federal No. 33-22-8-17:**NW SE Sec. 22-T8S-R17E**

Top Garden Gulch Member:	4194 feet
Garden Gulch Confining Zone:	4157 feet to 4194 feet
Top 80% EPA Cement Bond:	4153 feet to 4171 feet
Total Depth (Driller):	6350 feet

The 37-foot Confining Zone contains eighteen (18) feet of continuous 80% bond index cement bond. This annulus cement is considered adequate to confine the injectate to the authorized injection interval.

PART II. C.**Prior to Commencing Injection (Additional Wells)****(Condition 2)**

Canvasback No. 15-22-8-17: This document is being issued without authority to inject. Prior to beginning injection, the operator is required to submit the following information for EPA review and written approval:

- A successful **mechanical integrity test (MIT)** demonstrating Part I Internal MI (Enclosed);
- a **pore pressure calculation** of the proposed injection zone; and an
- EPA Form No. 7520-12 (**Well Rework Record**, enclosed).

Injection Interval

(Condition 3)

Injection shall be limited to the **gross Garden Gulch, Douglas Creek and Basal Carbonate Members of the Green River Formation from 4200 feet (KB) to the top of the Wasatch Formation, estimated to be 6575 feet (KB).**

Injection Pressure Limitation

(Condition 4)

Pursuant to Final Area Permit UT20855-00000, Part II. Section C. 5. (b) (1), the maximum allowable injection pressure (MAIP) *"...shall be determined for each Area Permit well as:" "(1) Using sand fracture treatment data, the EPA will calculate the MIP for each treated (sand/frac) interval using the instantaneous shut-in pressure (ISIP) from that interval. The minimum MIP calculated shall be the initial maximum surface injection pressure for that well;"*. A fracture gradient (FG) of 0.740 psi/ft is the minimum value FG calculated from the three (3) ISIP sand/frac treatments.

Until such time that a step-rate injectivity test (SRT) has been performed, reviewed, and approved by the EPA, the initial maximum allowable injection pressure (MAIP) for the **Canvasback No. 15-22-8-17** shall not exceed **1755 psig**.

$$\text{MAIP} = [\text{FG} - (0.433)(\text{SG}) \text{ D}]$$

$$\text{FG} = 0.740 \text{ psi/ft (Calculated from sd/frac ISIP)}$$

$$\text{SG} = 1.005$$

$$\text{D} = 5755 \text{ feet. Top perforation.}$$

$$\text{MAIP} = [0.740 - (0.433)(1.005) 5755]$$

$$\text{MAIP} = 1754 \text{ psig, but rounded up to } \mathbf{1755 \text{ psig.}}$$

Final Area Permit (UT20855-00000), has a provision whereby the operator may request an increase, or decrease, in the maximum surface injection pressure.

PART II. F.Demonstration of Financial Responsibility:

(Condition 1)

The current plugging and abandonment cost for the Canvasback No. 15-22-8-17 is estimated to be \$33,025.00. The applicant has chosen to demonstrate financial responsibility via a **Financial Statement** that has been reviewed and approved by the EPA.

PART III. E.

Reporting of Noncompliance:

(Condition 10)

- (a) Anticipated Noncompliance. The operator shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.
- (b) Compliance Schedules. Reports of compliance or noncompliance with, or any progress on, interim and final requirements contained in any compliance schedule of this Permit shall be submitted **no later than thirty (30) days following each schedule date.**
- (c) Written Notice of any noncompliance which may endanger health or the environment **shall be reported to the Director within five (5) days** of the time the operator becomes aware of the noncompliance. The written notice shall contain a description of the noncompliance and its cause; the period of noncompliance including dates and times; if the noncompliance has not been corrected the anticipated time it is expected to continue; and steps taken or planned to prevent or reduce recurrence of the noncompliance.

Twenty-Four Hour Noncompliance Reporting:

(Condition 11)

The operator shall report to the Director any noncompliance which may endanger health or environment. Information shall be provided, either orally or by leaving a message, within twenty-four (24) hours from the time the operator becomes aware of the circumstances by telephoning 1.800.227-8917 and asking for the **EPA Region VIII UIC Program Compliance and Enforcement Director**, or by contacting the **Region VIII Emergency Operations Center** at 303.293.1788 if calling from outside EPA Region VIII. The following information shall be included in the verbal report:

- (a) Any monitoring or other information which indicates that any contaminant may cause an endangerment to a USDW.
- (b) Any noncompliance with a Permit condition or malfunction of the injection system which may cause fluid migration into or between underground sources of drinking water.

Oil Spill and Chemical Release Reporting:

(Condition 12)

The operator shall comply with all other reporting requirements related to oil spills and chemical releases or other potential impacts to human health or the environment by contacting

the National Response Center (NRC) 1.800.424.8802 or 202.267.2675, or through the NRC website at <http://www.nrc.uscg.mil/index.htm>.

Other Noncompliance:

(Condition 13)

The operator shall report all other instances of noncompliance not otherwise reported at the time monitoring reports are submitted. The reports shall contain the information listed in Part III. 10. c. ii. of this Permit.

Other Information: Where the operator becomes aware that he failed to submit any relevant facts in the Permit application, or submitted incorrect information in a Permit application, or in any report to the Director, the operator shall submit such correct facts or information within two (2) weeks of the time such information became known to him.

APPENDIX C

PLUGGING AND ABANDONMENT: The Plugging and Abandonment (P&A) Plan (Application Attachment Q-2) submitted by the applicant has been reviewed and approved by the EPA. The P&A Plan is now consistent with EPA requirements to protect all USDWs. The permittee will place 9.2 ppg plugging gel or bentonite mud between all cement plugs.


PLUG NO. 1: Set a cast iron bridge plug (CIBP) at 5660 feet. Place 100 feet of Class "G" cement on top of CIBP.

PLUG NO. 2: Set a cement plug inside of the 5-1/2 inch casing from 2000 feet to 2200 feet over a water zone.

PLUG NO. 3: Perforate 4 jet shots per foot at 361 feet. Set Class "G" cement inside of 5-1/2 inch casing and in the 5-1/2 inch X 8-5/8 inch annulus from 361 feet to the surface.

This authorization for well conversion of the Canvasback No.15-22-8-17 to an injection well becomes effective upon signature.

Date: MAR 11 2005



Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

WELL REWORK RECORD

NAME AND ADDRESS OF CONTRACTOR

PERMIT NUMBER

____ 1/4 of ____ 1/4 of ____ 1/4 of ____ 1/4 of Section ____ Township ____ Range ____

and _____ ft. from (E/W) _____ Line of quarter section

Date Rework Completed

Well Number

Treatment Record

Treatment Record

Logged Intervals

DATE SIGNED



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

999 18th STREET - SUITE 500

DENVER, COLORADO 80202-2466

SUBJECT: GROUND WATER SECTION GUIDANCE NO. 39
Pressure testing injection wells for Part I (internal)
Mechanical Integrity

FROM: Tom Pike, Chief
UIC Direct Implementation Section

TO: All Section Staff
Montana Operations Office

Introduction

The Underground Injection Control (UIC) regulations require that an injection well have mechanical integrity at all times (40 CFR 144.28 (f)(2) and 40 CFR 144.51 (q)(1)). A well has mechanical integrity (40 CFR 146.8) if:

- (1) There is no significant leak in the tubing, casing or packer; and
- (2) There is no significant fluid movement into an underground source of drinking water (USDW) through vertical channels adjacent to the injection wellbore.

Definition: Mechanical Integrity Pressure Test for Part I. A pressure test used to determine the integrity of all the downhole components of an injection well, usually tubing, casing and packer. It is also used to test tubing cemented in the hole by using a tubing plug or retrievable packer. Pressure tests must be run at least once every five years. If for any reason the tubing/packer is pulled, the injection well is required to pass another mechanical integrity test of the tubing casing and packer prior to recommencing injection regardless of when the last test was conducted. Tests run by operators in the absence of an EPA inspector must be conducted according to these procedures and recorded on either the attached form or an equivalent form containing the necessary information. A pressure recording chart documenting the actual annulus test pressures must be attached to the form.

This guidance addresses making a determination of Part I of Mechanical Integrity (no leaks in the tubing, casing or packer). The Region's policy is: 1) to determine if there are significant leaks in the tubing, casing or packer; 2) to assure that the casing can withstand pressure similar to that which



Printed on Recycled Paper

would be applied if the tubing or packer fails; 3) to make the Region's test procedure consistent with the procedures utilized by other Region VIII Primacy programs; and 4) to provide a procedure which can be easily administered and is applicable to all class I and II wells. Although there are several methods allowed for determining mechanical integrity, the principal method involves running a pressure test of the tubing/casing annulus. Region VIII's procedure for running a pressure test is intended to aid UIC field inspectors who witness pressure tests for the purpose of demonstrating that a well has Part I of Mechanical Integrity. The guidance is also intended as a means of informing operators of the procedures required for conducting the test in the absence of an EPA inspector.

Pressure Test Description

Test Frequency

The mechanical integrity of an injection well must be maintained at all times. Mechanical integrity pressure tests are required at least every five (5) years. If for any reason the tubing/packer is pulled, however, the injection well is required to pass another mechanical integrity test prior to recommencing injection regardless of when the last test was conducted. The Regional UIC program must be notified of the workover and the proposed date of the pressure test. The well's test cycle would then start from the date of the new test if the well passes the test and documentation is adequate. Tests may be required on a more frequent basis depending on the nature of the injectate and the construction of the well (see Section guidance on MITs for wells with cemented tubing and regulations for Class I wells).

Region VIII's criteria for well testing frequency is as follows:

1. Class I hazardous waste injection wells; initially [40 CFR 146.68(d) (1)] and annually thereafter;
2. Class I non-hazardous waste injection wells; initially and every two (2) years thereafter, except for old permits (such as the disposal wells at carbon dioxide extraction plants which require a test at least every five years);
3. Class II wells with tubing, casing and packer; initially and at least every five (5) years thereafter;
4. Class II wells with tubing cemented in the hole; initially and every one (1) or two (2) years thereafter



depending on well specific conditions (See Region VIII UIC Section Guidance #36);

5. Class II wells which have been temporarily abandoned (TAd) must be pressure tested after being shut-in for two years; and
6. Class III uranium extraction wells; initially.

Test Pressure

To assure that the test pressure will detect significant leaks and that the casing is subjected to pressure similar to that which would be applied if the tubing or packer fails, the tubing/casing annulus should be tested at a pressure equal to the maximum allowed injection pressure or 1000 psig whichever is less. The annular test pressure must, however, have a difference of at least 200 psig either greater or less than the injection tubing pressure. Wells which inject at pressures of less than 300 psig must test at a minimum pressure of 300 psig, and the pressure difference between the annulus and the injection tubing must be at least 200 psi.

Test Criteria

1. The duration of the pressure test is 30 minutes.
2. Both the annulus and tubing pressures should be monitored and recorded every five (5) minutes.
3. If there is a pressure change of 10 percent or more from the initial test pressure during the 30 minute duration, the well has failed to demonstrate mechanical integrity and should be shut-in until it is repaired or plugged.
4. A pressure change of 10 percent or more is considered significant. If there is no significant pressure change in 30 minutes from the time that the pressure source is disconnected from the annulus, the test may be completed as passed.

Recordkeeping and Reporting

The test results must be recorded on the attached form. The annulus pressure should be recorded at five (5) minute intervals. Tests run by operators in the absence of an EPA inspector must be conducted according to these procedures and recorded on the attached form or an equivalent form and a pressure recording



chart documenting the actual annulus test pressures must be attached to the submittal. The tubing pressure at the beginning and end of each test must be recorded. The volume of the annulus fluid bled back at the surface after the test should be measured and recorded on the form. This can be done by bleeding the annulus pressure off and discharging the associated fluid into a five gallon container. The volume information can be used to verify the approximate location of the packer.

Procedures for Pressure Test

1. Scheduling the test should be done at least two (2) weeks in advance.
2. Information on the well completion (location of the packer, location of perforations, previous cement work on the casing, size of casing and tubing, etc.) and the results of the previous MIT test should be reviewed by the field inspector in advance of the test. Regional UIC Guidance #35 should also be reviewed. Information relating to the previous MIT and any well workovers should be reviewed and taken into the field for verification purposes.
3. All Class I wells and Class II SWD wells should be shut-in prior to the test. A 12 to 24-hour shut-in is preferable to assure that the temperature of the fluid in the wellbore is stable.
4. Class II enhanced recovery wells may be operating during the test, but it is recommended that the well be shut-in if possible.
5. The operator should fill the casing/tubing annulus with inhibited fluid at least 24 hours in advance, if possible. Filling the annulus should be undertaken through one valve with the second valve open to allow air to escape. After the operator has filled the annulus, a check should be made to assure that the annulus will remain full. If the annulus can not maintain a full column of fluid, the operator should notify the Director and begin a rework. The operator should measure and report the volume of fluid added to the annulus. If not already the case, the casing/tubing valves should be closed, at least, 24 hours prior to the pressure test.

Following steps are at the well:

6. Read tubing pressure and record on the form. If the



well is shut-in, the reported information on the actual maximum operating pressure should be used to determine test pressures.

7. Read pressure on the casing/tubing annulus and record value on the form. If there is pressure on the annulus, it should be bled off prior to the test. If the pressure will not bleed-off, the guidance on well failures (Region VIII UIC Section Guidance #35) should be followed.
8. Ask the operator for the date of the last workover and the volume of fluid added to the annulus prior to this test and record information on the form.
9. Hook-up well to pressure source and apply pressure until test value is reached.
10. Immediately disconnect pressure source and start test time (If there has been a significant drop in pressure during the process of disconnection, the test may have to be restarted). The pressure gages used to monitor injection tubing pressure and annulus pressure should have a pressure range which will allow the test pressure to be near the mid-range of the gage. Additionally, the gage must be of sufficient accuracy and scale to allow an accurate reading of a 10 percent change to be read. For instance, a test pressure of 600 psi should be monitored with a 0 to 1000 psi gage. The scale should be incremented in 20 psi increments.
11. Record tubing and annulus pressure values every five (5) minutes.
12. At the end of the test, record the final tubing pressure.
13. If the test fails, check the valves, bull plugs and casing head close up for possible leaks. The well should be retested.
14. If the second test indicates a well failure, the Region should be informed of the failure within 24 hours by the operator, and the well should be shut-in within 48 hours per Headquarters guidance #76. A follow-up letter should be prepared by the operator which outlines the cause of the MIT failure and proposes a potential course of action. This report should be submitted to EPA within five days.



15. Bleed off well into a bucket, if possible, to obtain a volume estimate. This should be compared to the calculated value obtained using the casing/tubing annulus volume and fluid compressibility values.

16. Return to office and prepare follow-up.

Alternative Test Option

While it is expected that the test procedure outlined above will be applicable to most wells, the potential does exist that unique circumstances may exist for a given well that precludes or makes unsafe the application of this test procedure. In the event that these exceptional or extraordinary conditions are encountered, the operator has the option to propose an alternative test or monitoring procedures. The request must be submitted by the operator in writing and must be approved in writing by the UIC-Implementation Section Chief or equivalent level of management.

Attachment



Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program, UIC Direct Implementation Program 8P-W-GW
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: ____/____/____

Test conducted by: _____

Others present: _____

Well Name: _____	Type: ER SWD	Status: AC TA UC
Field: _____		
Location: _____	Sec: _____ T _____ N/S R _____ E/W	County: _____ State: _____
Operator: _____		
Last MIT: ____/____/____	Maximum Allowable Pressure: _____	PSIG

Is this a regularly scheduled test? ☐ Yes ☐ No

Initial test for permit? ☐ Yes ☐ No

Test after well rework? ☐ Yes ☐ No

Well injecting during test? ☐ Yes ☐ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: _____ psig

MIT DATA TABLE		Test #1	Test #2	Test #3
TUBING PRESSURE				
Initial Pressure	psig	psig	psig	psig
End of test pressure	psig	psig	psig	psig
CASING / TUBING ANNULUS PRESSURE				
0 minutes	psig	psig	psig	psig
5 minutes	psig	psig	psig	psig
10 minutes	psig	psig	psig	psig
15 minutes	psig	psig	psig	psig
20 minutes	psig	psig	psig	psig
25 minutes	psig	psig	psig	psig
30 minutes	psig	psig	psig	psig
minutes	psig	psig	psig	psig
minutes	psig	psig	psig	psig
RESULT	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☐ No

Canvasback #15-22-8-17

Spud Date: 2/21/2003
Put on Production: 4/24/2003
GL: 5168' KB: 5189'

Initial Production: 63 BOPD,
63 MCFD, 20 BWPD

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24# *Base 11900's* *< 50'*
LENGTH: 7 jts. (304.08')
DEPTH LANDED: 310.08' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 250 sxs Class "G" cmt. Estimated 10 bbls cmt. to surface.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 147 jts. (6301.92')
DEPTH LANDED: 6299.92' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 310 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.
CEMENT TOP AT: 400'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 189 jts (6107.23')
TUBING ANCHOR: 6119.23' KB
NO. OF JOINTS: 1 jt (32.33')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 6154.36' KB
NO. OF JOINTS: 2 jts. (64.88')
TOTAL STRING LENGTH: BOT @ 6220.79' KB

Proposed Injection Wellbore Diagram

FRAC JOB

4/21/03 6158'-6295' Frac CP2, CP3, and CP4 sands as follows:
98,671# 20/40 sand in 424 bbls 1-25 Viking fluid. Treated @ avg press of 1800 psi w/avg rate of 27.0 BPM. ISIP 2020 psi. Calc flush: 6156 gal. Actual flush: 5947 gal.
4/21/03 6054'-6105' Frac CP .5 and CP1 sands as follows:
78,834# 20/40 sand in 343 bbls 1-25 Viking fluid. Treated @ avg press of 2400 psi w/avg rate of 25.5 BPM. ISIP 1850 psi. Calc flush: 6052 gal. Actual flush: 5843 gal.
4/21/03 5755'-5777' Frac LODC sands as follows:
19,757# 20/40 sand in 91 bbls 1-25 Viking fluid. Treated @ avg press of 2375 psi w/avg rate of 26.0 BPM. ISIP 1790 psi. Calc flush: 5753 gal. Actual flush: 5843 gal.

2708

80% Bond Index Cement

- 4756' - 4200' Confining Zone
- 4200' Garden Gulch Mem

- 5194' Trough Creek Mem

5958'

Packer @ 5720'

5755'-5759'

5773'-5777'

6054'-6061'

6084'-6090'

6094'-6105'

6158'-6171'

6205'-6214'

6216'-6227'

6285'-6295'

PBTD @ 6318'

SHOE @ 6300'

TD @ 6318'

PERFORATION RECORD

4/14/03	6216'-6227'	4 JSPF	44 holes
4/14/03	6205'-6214'	4 JSPF	36 holes
4/14/03	6158'-6171'	4 JSPF	52 holes
4/21/03	6285'-6295'	4 JSPF	40 holes
4/21/03	6094'-6105'	4 JSPF	44 holes
4/21/03	6084'-6090'	4 JSPF	24 holes
4/21/03	6054'-6061'	4 JSPF	28 holes
4/21/03	5773'-5777'	4 JSPF	16 holes
4/21/03	5755'-5759'	4 JSPF	16 holes



Inland Resources Inc.

Canvasback #15-22-8-17

910' FSL & 2056' FEL

SW/SE Section 22-T8S-R17E

Duchesne Co, Utah

API #43-013-32240; Lease #UTU-77233

Est. Basal Carbonate 6450
Est. Wasatch 6575'

MC 5/5/04

016

4301332340



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

MAR 22 2005

RECEIVED

MAR 23 2005

DIV. OF OIL, GAS & MINING

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Mr. Mike Guinn
Vice President - Operations
Newfield Production Co.
Route 3 - Box 3630
Myton, Utah 84502

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RE: ADDITIONAL WELL TO AREA PERMIT
Canvasback Area Permit: UT20855-00000
Canvasback Federal No. 13-23-8-17
Well ID: 20855-06520
NW SW Sec. 23 - T8S - 17E
Duchesne County, Utah

Dear Mr. Guinn:

The Newfield Production Co. (Newfield) request to convert a former Green River Formation oil well, the Canvasback Federal No. 13-23-8-17, to a Garden Gulch-Douglas Creek-Basal Carbonate Members of the Green River Formation enhanced recovery injection well in the Canvasback Area Permit is hereby authorized. The proposed Canvasback Federal No. 13-23-8-17 Class II enhanced recovery injection well is within the exterior boundary of the Canvasback Area Permit UT20855-00000; is within the exterior boundary of the Uintah & Ouray Indian Reservation; and the addition is being made under the authority of 40 CFR § 144.33 (c) and the terms of the Area Permit. Unless specifically mentioned in the enclosed Authorization For An Additional Well, all terms and conditions of the original Area Permit will apply to the conversion, operation, monitoring, and plugging and abandonment of the Canvasback Federal No. 13-23-8-17.



Printed on Recycled Paper

Prior to beginning injection, the Environmental Protection Agency (EPA) requires that Newfield submit for review and approval (1) the results of a **Part I (Internal) mechanical integrity test** (Guidance enclosed), (2) a **pore pressure** calculation of the injection interval, (3) an **EPA Form No. 7520-12** (Well Rework Record, enclosed).

Part II. Section C. Condition No. 5 (b) (1), (Injection Pressure Limitation), Canvasback Area Permit (UT20855-00000) , cites the method by which the maximum initial allowable injection pressure (MAIP) shall be calculated for each Additional Well to the Canvasback Area Permit. As a result, the MAIP for the Canvasback Federal No. 13-23-8-17 shall not exceed **1365 psig**. The Canvasback Area Permit, Part II. C. 5., provides an opportunity for the permittee to request an increase, or decrease, in the initial maximum surface injection pressure.

Please be aware that Newfield does not have authorization to begin injection into the Canvasback Federal No. 13-23-8-17 until the Prior to Commencing Injection requirements, listed above, have been submitted and evaluated by the EPA, and Newfield has received written authorization to begin injection from the Assistant Regional Administrator, or the Assistant Regional Administrator's authorized representative.

If Newfield has any questions, please call Mr. Dan Jackson at (800) 227-8917 (Ext. 6155), or in the Denver area at (303) 312-6155. Please submit the required pre-authorization to inject data to **ATTENTION: DAN JACKSON**, at the letterhead address, citing **MAIL CODE: 8P-W-GW** very prominently.

Sincerely,



Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

enclosures: Authorization For Conversion of An Additional Well
EPA Form No. 7520-12 (Well Rework Record)
Guidance No. 39: Part I Mechanical Integrity (Internal)
Schematic Diagram: Proposed Conversion

cc w/ enclosures: Maxine Natchees
Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe

Elaine Willie
Environmental Coordinator
Ute Indian Tribe

Chester Mills
Superintendent
Bureau of Indian Affairs
Uintah & Ouray Indian Agency

David Gerbig
Operations Engineer
Newfield Production Company

Gil Hunt
Technical Services Manager
State of Utah - Natural Resources

Kirk Fleetwood
Sr. Petroleum Engineer
Bureau of Land Management
Vernal District



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 300
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

**AUTHORIZATION FOR AN ADDITIONAL WELL
TO THE
CANVASBACK AREA PERMIT: UT20855-00000**

The Environmental Protection Agency (EPA) authorizes the inclusion of an additional enhanced recovery injection well to the Canvasback Area Permit No. UT20855-00000, as authorized by 40 CFR § 144.33 (c). The additional well is described as:

WELL NAME: CANVASBACK FEDERAL NO. 13-23-8-17

WELL PERMIT NUMBER: UT20855-06520

**SURFACE LOCATION: 306' FSL & 642' FWL (SW SW)
Sec. 22 - T8S - R17E
Duchesne County, Utah.**

This well is subject to all provisions of the original Canvasback Area Permit No. UT20855-00000, and subsequent Modifications, unless specifically detailed below:

UNDERGROUND SOURCE OF DRINKING WATER (USDW): The base of the USDW (Total Dissolved Solids less than 10,000 mg/l) in the Canvasback Federal No.13-23-8-17 occurs within the Uinta Formation **less than 80 feet** from ground level (GL). The source for the location of the base of the USDW is the STATE OF UTAH: PUBLICATION NO. 2. BASE OF MODERATELY SALINE GROUND WATER IN THE UINTA BASIN, UTAH. Surface casing was set at **310 feet** kelly bushing (KB) and cemented to the surface.

Reference: <http://NRWRT1.NR.STATE.UT.US...> Water Rights...Queries...POD: Within the one-quarter (1/4) mile Area-of-Review (AOR) around the Canvasback Federal No.13-23-8-17 there are no reservoirs, streams, springs or wells.

WATER ANALYSES:

Produced Green River Formation Water: (7/15/04) **13,367 mg/l TDS.**

Source Water: Johnson Water District Reservoir. (3/31/04) **400 mg/l TDS.**

Blended Injectate: (7/21/01) **7761 mg/l TDS.**



CONFINING ZONE REVIEW: CANVASBACK FEDERAL NO. 13-23-8-17

The EPA has authorized the gross interval from the top of the Garden Gulch Member to the top of the Wasatch as the enhanced recovery injection interval within the Canvasback Area Permit. Overlying the top of the Garden Gulch Member (4178 feet), in the Canvasback Federal No. 13-23-8-17, are forty-six (46) feet (4132 feet to 4178 feet) of Green River Formation black, slightly silty, impervious shale which forms an effective lithologic confining zone.

INJECTION ZONE REVIEW: CANVASBACK FEDERAL NO. 13-23-8-17

The Canvasback Final Area Permit (Effective August 18, 2000) authorized injection into the Garden Gulch and Douglas Creek Members of the Green River Formation. By Major Permit Modification No. 3 (Effective September 10, 2003) the EPA authorized the gross Green River Formation Garden Gulch-Douglas Creek-Basal Carbonate Members as the enhanced recovery injection interval for the Canvasback Area Permit. This Modification also recognized the Federal No. 1-26 (NE NW Sec. 26 - T8S - R17E), UIC Permit No. UT20702-04671, as the TYPE WELL for identifying the tops of the Garden Gulch Member, the Douglas Creek Member, the Basal Carbonate Member, the top of the Wasatch Formation and the "Confining Zone" overlying the top of the Garden Gulch Member.

The authorized injection zone for the Canvasback Federal No. 13-23-8-17 will be from the Garden Gulch Member (4178 feet) to the top of the Wasatch Formation (Estimated to be 6543 feet).

Lithologically, the gross authorized enhanced recovery injection interval, Garden Gulch to the top of the Wasatch Formation, is fluvial and lacustrine shale, fluvial and lacustrine sandstone, lacustrine marlstone, and limestone. The Uinta and Green River Formations are predominantly non-lacustrine fluvial shale and sandstone on the basin margins, whereas lacustrine deposition predominates in the central basin area for these two formations. The Wasatch Formation is predominantly fluvial, except for increasing minor lacustrine deposition in the central basin area.

WELL CONSTRUCTION REVIEW: CANVASBACK FEDERAL NO. 13-23-8-17.

SURFACE CASING: 8-5/8 inch casing is set at 316 feet (KB) in a 12-1/4 inch hole, using 140 sacks of Class "G" cement circulated to the surface. The base of the USDW is less than eighty (80) feet from ground level.

LONGSTRING CASING: 5-1/2 inch casing is set at 6408 feet (KB) in a 7-7/8 inch hole, and cemented with 320 sacks of Premium Lite II mixed and 400 sacks of 50/50 Pozmix.

The operator identifies the top of cement at 290 feet.

The EPA analysis of the CBL/GR identifies 80% cement bond index across the Garden Gulch Member confining zone from 4122 feet to 4174 feet.

An EPA analysis of the Canvasback Federal No. 13-23-8-17 CBL/GR did identify 80% bond index cement bond across the Garden Gulch Member confining zone, pursuant to standards of Region 8 GROUND WATER SECTION GUIDANCE NO. 34: Cement Bond Logging Techniques and Interpretation. Therefore, **it has been determined that the cement in this well provides an effective barrier** to significant upward movement of fluids through vertical channels adjacent to the wellbore, pursuant to 40 CFR 146.8 (a) (2).

PART II. A. CONSTRUCTION REQUIREMENTS FOR ADDITIONAL WELLS

Tubing and Packer:

(Condition 3)

For injection purposes, the Canvasback Federal No. 13-23-8-17 shall be equipped with 2-7/8 tubing with a packer to be set at a depth no higher than 100 feet above the top perforation.

Formation Testing and Logging

(Condition 6)

- (a) Upon conversion of the Canvasback Federal No. 13-23-8-17, the permittee is required to determine the injection zone **fluid pore pressure** (static bottom hole pressure) prior to commencement of enhanced recovery injection operation. The results of this test shall be submitted to the EPA.
- (b) A **Step-Rate Test (SRT)** shall be performed on the Canvasback Federal No. 13-23-8-17 within three (3) to six (6) months after injection operations are initiated and the results submitted to the EPA. The permittee may contact the EPA prior to conducting the SRT to acquire the most current Guidance for conducting the SRT.

PART II. B.

Corrective Action

As of March 2005, there are two (2) active Green River oil wells within or proximate to the one-quarter (1/4) mile radius around the Canvasback Federal No. 13-23-8-17-8-17. No wells need Corrective Action.

Garden Gulch-Douglas Creek Members Oil Wells:

<u>Greater Boundary No. 4-26-8-17:</u>	NW NW Sec. 26 -T8S-R17E
Top Garden Gulch Member:	4100 feet
Garden Gulch Confining Zone:	4055 feet to 4100 feet
Top 80% EPA Cement Bond:	4369 feet - 4400 feet
Top Douglas Creek Member:	5104 feet
Total Depth (Driller):	6332 feet in Douglas Creek Member

The 45-foot confining shale (4055 feet to 4100 feet) overlying the top of the Garden Gulch Member (4183 feet) is not protected by 80% bond index cement bond. This lack of confining zone annulus cement may not prevent upward movement of injected fluids through vertical channels adjacent to the well bore. The permittee will be required to inspect the surface of this location for fluid leaks on a weekly basis. **Any observation of surface leakage may be considered as noncompliance with the Canvasback Federal No. 13-23-8-17 Permit.** The Canvasback Federal No.13-23-8-17 shall suspend operations immediately, and will stay suspended until the noncompliance has been resolved, and renewed injection has been approved in writing by the Director.

<u>Canvasback No. 16-22-8-17 :</u>	SE SE Sec. 22-T8S-R17E
Top Garden Gulch Member:	4198 feet
Garden Gulch Confining Zone:	4154 feet to 4198 feet
Top 80% EPA Cement Bond:	3844 feet - 4128 feet and 4228 feet - 4362 feet.
Top Douglas Creek Member:	5176 feet
Total Depth (Driller):	6379 feet in Douglas Creek Member.

The 44-foot confining shale (4154 feet to 4198 feet) overlying the top of the Garden Gulch Member (4198 feet) is not protected by 80% bond index cement bond. This lack of confining zone annulus cement may not prevent upward movement of injected fluids through vertical channels adjacent to the well bore. The permittee will be required to inspect the surface of this location for fluid leaks on a weekly basis. **Any observation of surface leakage may be considered as noncompliance with the Canvasback Federal No. 13-23-8-17 Permit.** The Canvasback Federal No. 13-23-8-17 shall suspend operations immediately, and will stay suspended until the noncompliance has been resolved, and renewed injection has been approved in writing by the Director.

PART II. C.

Prior to Commencing Injection (Additional Wells)

(Condition 2)

Canvasback Federal No. 13-23-8-17: This document is being issued without authority to inject. Prior to beginning injection, the operator is required to submit the following information for EPA review and written approval:

- A successful **mechanical integrity test (MIT)** demonstrating Part I Internal MI (Enclosed);
- a **pore pressure calculation** of the proposed injection zone; and an
- EPA Form No. 7520-12 (**Well Rework Record**, enclosed).

Injection Interval

(Condition 3)

Injection shall be limited to the **gross Garden Gulch, Douglas Creek and Basal Carbonate Members of the Green River Formation** from 4178 feet (KB) to the top of the Wasatch Formation, estimated to be 6543 feet (KB).

Injection Pressure Limitation

(Condition 4)

Pursuant to Final Area Permit UT20855-00000, Part II. Section C. 5. (b), the maximum allowable injection pressure (MAIP) "...shall be determined for each Area Permit well as:" "(1) Using sand fracture treatment data, the EPA will calculate the MIP for each treated (sand/frac) interval using the instantaneous shut-in pressure (ISIP) from that interval. The minimum MIP calculated shall be the initial maximum surface injection pressure for that well;". A fracture gradient (FG) of 0.720 psi/ft is the minimum value FG calculated from the six (6) ISIP sand/frac treatments. The 0.720 FG is acceptable for calculation of the **initial Maximum Allowable Injection Pressure**.

Until such time that a step-rate injectivity test (SRT) has been performed, reviewed, and approved by the EPA, the **initial maximum allowable injection pressure (MAIP)** for the **Canvasback Federal No. 13-23-8-17** shall not exceed **1365psig**.

$$\begin{aligned}
 \text{MAIP} &= [\text{FG} - (0.433)(\text{SG}) \text{ D}] \\
 \text{FG} &= 0.720 \text{ psi/ft (Calculated from sd/frac ISIP)} \\
 \text{SG} &= 1.005 \\
 \text{D} &= 4786 \text{ feet. Top perforation.} \\
 \text{MAIP} &= [0.740 - (0.433)(1.005) 5755] \\
 \text{MAIP} &= 1363 \text{ psig, but rounded up to } \mathbf{1365 \text{ psig.}}
 \end{aligned}$$

Final Area Permit (UT20855-00000), has a provision whereby the operator may request an increase, or decrease, in the maximum surface injection pressure.

PART II. F.

Demonstration of Financial Responsibility:

(Condition 1)

The current plugging and abandonment cost for the Canvasback Federal No. 13-23-8-17 is estimated to be \$33,025.00. The applicant has chosen to demonstrate financial responsibility via a **Financial Statement** that has been reviewed and approved by the EPA.

PART III. E.

Reporting of Noncompliance:

(Condition 10)

- (a) Anticipated Noncompliance. The operator shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.
- (b) Compliance Schedules. Reports of compliance or noncompliance with, or any progress on, interim and final requirements contained in any compliance schedule of this Permit shall be submitted **no later than thirty (30) days following each schedule date.**
- (c) Written Notice of any noncompliance which may endanger health or the environment **shall be reported to the Director within five (5) days** of the time the operator becomes aware of the noncompliance. The written notice shall contain a description of the noncompliance and its cause; the period of noncompliance including dates and times; if the noncompliance has not been corrected the anticipated time it is expected to continue; and steps taken or planned to prevent or reduce recurrence of the noncompliance.

Twenty-Four Hour Noncompliance Reporting:

(Condition 11)

The operator shall report to the Director any noncompliance which may endanger health or environment. Information shall be provided, either orally or by leaving a message, within twenty-four (24) hours from the time the operator becomes aware of the circumstances by telephoning 1.800.227-8917 and asking for the **EPA Region VIII UIC Program Compliance and Enforcement Director**, or by contacting the **Region VIII Emergency Operations Center** at 303.293.1788 if calling from outside EPA Region VIII. The following information shall be included in the verbal report:

- (a) Any monitoring or other information which indicates that any contaminant may cause an endangerment to a USDW.

- (b) Any noncompliance with a Permit condition or malfunction of the injection system which may cause fluid migration into or between underground sources of drinking water.

Oil Spill and Chemical Release Reporting:

(Condition 12)

The operator shall comply with all other reporting requirements related to oil spills and chemical releases or other potential impacts to human health or the environment by contacting the National Response Center (NRC) 1.800.424.8802 or 202.267.2675, or through the NRC website at <http://www.nrc.uscg.mil/index.htm>.

Other Noncompliance:

(Condition 13)

The operator shall report all other instances of noncompliance not otherwise reported at the time monitoring reports are submitted. The reports shall contain the information listed in Part III. 10. c. ii. of this Permit.

Other Information: Where the operator becomes aware that he failed to submit any relevant facts in the Permit application, or submitted incorrect information in a Permit application, or in any report to the Director, the operator shall submit such correct facts or information within two (2) weeks of the time such information became known to him.

APPENDIX C

PLUGGING AND ABANDONMENT: The Plugging and Abandonment (P&A) Plan (Application Attachment Q-2) submitted by the applicant has been reviewed and modified by the EPA. The EPA has added Plug No. 4. The P&A Plan is now consistent with EPA requirements to protect all USDWs. The permittee will place 9.2 ppg plugging gel or bentonite mud between all cement plugs.

PLUG NO. 1: Set a cast iron bridge plug (CIBP) at 4690 feet. Place 100 feet of Class "G" cement on top of CIBP.


PLUG NO. 2: Set a cement plug inside of the 5-1/2 inch casing from 2000 feet to 2200 feet over a water zone.

PLUG NO. 3: Set a cement plug inside of the 5-1/2 inch casing from surface to a depth of 366 feet.

PLUG NO. 4: Set a cement plug in the annulus between the 5-1/2 inch casing and the 8-5/8 inch casing from the surface to a depth of 366 feet.

This authorization for well conversion of the Canvasback Federal No.13-23-8-17 to a Class II enhanced recovery injection well becomes effective upon signature.

Date: MAR 22 2005



Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

WELL REWORK RECORD

NAME AND ADDRESS OF CONTRACTOR

STATE

COUNTY

UNIT NUMBER

1/4 of ____ 1/4 of ____ 1/4 of ____ 1/4 of Section ____ Township ____ Range ____

Surface _____
Location _____ ft. from (N/S) _____ Line of quarter section
and _____ ft. from (E/W) _____ Line of quarter section

☐ Brine Disposal
☐ Enhanced Recovery
☐ Hydrocarbon Storage

Lease Name**Total Depth After Rework****Date Rework Commenced****Date Rework Completed**☐ Individual☐ Area

Number of Wells.

Well Number

Casing

Stop

Depth

Comment

Sacks

Type _____

Perforations

From

To _____

Acid or Fracture Treatment Record

Casing

Size

Depth

Cement

Sacks

Type _____

Perforations

From

To

Acid or Fracture Treatment Record

WIRE LINE LOGS, LIST EACH TYPE

Log Types

Logged Intervals

I certify under the penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment. (Ref. 40 CFR 144.32).

SIGNATURE

DATE SIGNED _____



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION VIII

999 18th STREET - SUITE 500

DENVER, COLORADO 80202-2466

SUBJECT: GROUND WATER SECTION GUIDANCE NO. 39
Pressure testing injection wells for Part I (internal)
Mechanical Integrity

FROM: Tom Pike, Chief
UIC Direct Implementation Section

TO: All Section Staff
Montana Operations Office

Introduction

The Underground Injection Control (UIC) regulations require that an injection well have mechanical integrity at all times (40 CFR 144.28 (f)(2) and 40 CFR 144.51 (q)(1)). A well has mechanical integrity (40 CFR 146.8) if:

- (1) There is no significant leak in the tubing, casing or packer; and
- (2) There is no significant fluid movement into an underground source of drinking water (USDW) through vertical channels adjacent to the injection wellbore.

Definition: Mechanical Integrity Pressure Test for Part I. A pressure test used to determine the integrity of all the downhole components of an injection well, usually tubing, casing and packer. It is also used to test tubing cemented in the hole by using a tubing plug or retrievable packer. Pressure tests must be run at least once every five years. If for any reason the tubing/packer is pulled, the injection well is required to pass another mechanical integrity test of the tubing casing and packer prior to recommencing injection regardless of when the last test was conducted. Tests run by operators in the absence of an EPA inspector must be conducted according to these procedures and recorded on either the attached form or an equivalent form containing the necessary information. A pressure recording chart documenting the actual annulus test pressures must be attached to the form.

This guidance addresses making a determination of Part I of Mechanical Integrity (no leaks in the tubing, casing or packer). The Region's policy is: 1) to determine if there are significant leaks in the tubing, casing or packer; 2) to assure that the casing can withstand pressure similar to that which



Printed on Recycled Paper

would be applied if the tubing or packer fails; 3) to make the Region's test procedure consistent with the procedures utilized by other Region VIII Primacy programs; and 4) to provide a procedure which can be easily administered and is applicable to all class I and II wells. Although there are several methods allowed for determining mechanical integrity, the principal method involves running a pressure test of the tubing/casing annulus. Region VIII's procedure for running a pressure test is intended to aid UIC field inspectors who witness pressure tests for the purpose of demonstrating that a well has Part I of Mechanical Integrity. The guidance is also intended as a means of informing operators of the procedures required for conducting the test in the absence of an EPA inspector.

Pressure Test Description

Test Frequency

The mechanical integrity of an injection well must be maintained at all times. Mechanical integrity pressure tests are required at least every five (5) years. If for any reason the tubing/packer is pulled, however, the injection well is required to pass another mechanical integrity test prior to recommencing injection regardless of when the last test was conducted. The Regional UIC program must be notified of the workover and the proposed date of the pressure test. The well's test cycle would then start from the date of the new test if the well passes the test and documentation is adequate. Tests may be required on a more frequent basis depending on the nature of the injectate and the construction of the well (see Section guidance on MITs for wells with cemented tubing and regulations for Class I wells).

Region VIII's criteria for well testing frequency is as follows:

1. Class I hazardous waste injection wells; initially [40 CFR 146.68(d)(1)] and annually thereafter;
2. Class I non-hazardous waste injection wells; initially and every two (2) years thereafter, except for old permits (such as the disposal wells at carbon dioxide extraction plants which require a test at least every five years);
3. Class II wells with tubing, casing and packer; initially and at least every five (5) years thereafter;
4. Class II wells with tubing cemented in the hole; initially and every one (1) or two (2) years thereafter



depending on well specific conditions (See Region VIII UIC Section Guidance #36);

5. Class II wells which have been temporarily abandoned (TAd) must be pressure tested after being shut-in for two years; and
6. Class III uranium extraction wells; initially.

Test Pressure

To assure that the test pressure will detect significant leaks and that the casing is subjected to pressure similar to that which would be applied if the tubing or packer fails, the tubing/casing annulus should be tested at a pressure equal to the maximum allowed injection pressure or 1000 psig whichever is less. The annular test pressure must, however, have a difference of at least 200 psig either greater or less than the injection tubing pressure. Wells which inject at pressures of less than 300 psig must test at a minimum pressure of 300 psig, and the pressure difference between the annulus and the injection tubing must be at least 200 psi.

Test Criteria

1. The duration of the pressure test is 30 minutes.
2. Both the annulus and tubing pressures should be monitored and recorded every five (5) minutes.
3. If there is a pressure change of 10 percent or more from the initial test pressure during the 30 minute duration, the well has failed to demonstrate mechanical integrity and should be shut-in until it is repaired or plugged.
4. A pressure change of 10 percent or more is considered significant. If there is no significant pressure change in 30 minutes from the time that the pressure source is disconnected from the annulus, the test may be completed as passed.

Recordkeeping and Reporting

The test results must be recorded on the attached form. The annulus pressure should be recorded at five (5) minute intervals. Tests run by operators in the absence of an EPA inspector must be conducted according to these procedures and recorded on the attached form or an equivalent form and a pressure recording



chart documenting the actual annulus test pressures must be attached to the submittal. The tubing pressure at the beginning and end of each test must be recorded. The volume of the annulus fluid bled back at the surface after the test should be measured and recorded on the form. This can be done by bleeding the annulus pressure off and discharging the associated fluid into a five gallon container. The volume information can be used to verify the approximate location of the packer.

Procedures for Pressure Test

1. Scheduling the test should be done at least two (2) weeks in advance.
2. Information on the well completion (location of the packer, location of perforations, previous cement work on the casing, size of casing and tubing, etc.) and the results of the previous MIT test should be reviewed by the field inspector in advance of the test. Regional UIC Guidance #35 should also be reviewed. Information relating to the previous MIT and any well workovers should be reviewed and taken into the field for verification purposes.
3. All Class I wells and Class II SWD wells should be shut-in prior to the test. A 12 to 24-hour shut-in is preferable to assure that the temperature of the fluid in the wellbore is stable.
4. Class II enhanced recovery wells may be operating during the test, but it is recommended that the well be shut-in if possible.
5. The operator should fill the casing/tubing annulus with inhibited fluid at least 24 hours in advance, if possible. Filling the annulus should be undertaken through one valve with the second valve open to allow air to escape. After the operator has filled the annulus, a check should be made to assure that the annulus will remain full. If the annulus can not maintain a full column of fluid, the operator should notify the Director and begin a rework. The operator should measure and report the volume of fluid added to the annulus. If not already the case, the casing/tubing valves should be closed, at least, 24 hours prior to the pressure test.

Following steps are at the well:

6. Read tubing pressure and record on the form. If the



well is shut-in, the reported information on the actual maximum operating pressure should be used to determine test pressures.

7. Read pressure on the casing/tubing annulus and record value on the form. If there is pressure on the annulus, it should be bled off prior to the test. If the pressure will not bleed-off, the guidance on well failures (Region VIII UIC Section Guidance #35) should be followed.
8. Ask the operator for the date of the last workover and the volume of fluid added to the annulus prior to this test and record information on the form.
9. Hook-up well to pressure source and apply pressure until test value is reached.
10. Immediately disconnect pressure source and start test time (If there has been a significant drop in pressure during the process of disconnection, the test may have to be restarted). The pressure gages used to monitor injection tubing pressure and annulus pressure should have a pressure range which will allow the test pressure to be near the mid-range of the gage. Additionally, the gage must be of sufficient accuracy and scale to allow an accurate reading of a 10 percent change to be read. For instance, a test pressure of 600 psi should be monitored with a 0 to 1000 psi gage. The scale should be incremented in 20 psi increments.
11. Record tubing and annulus pressure values every five (5) minutes.
12. At the end of the test, record the final tubing pressure.
13. If the test fails, check the valves, bull plugs and casing head close up for possible leaks. The well should be retested.
14. If the second test indicates a well failure, the Region should be informed of the failure within 24 hours by the operator, and the well should be shut-in within 48 hours per Headquarters guidance #76. A follow-up letter should be prepared by the operator which outlines the cause of the MIT failure and proposes a potential course of action. This report should be submitted to EPA within five days.



15. Bleed off well into a bucket, if possible, to obtain a volume estimate. This should be compared to the calculated value obtained using the casing/tubing annulus volume and fluid compressibility values.
16. Return to office and prepare follow-up.

Alternative Test Option

While it is expected that the test procedure outlined above will be applicable to most wells, the potential does exist that unique circumstances may exist for a given well that precludes or makes unsafe the application of this test procedure. In the event that these exceptional or extraordinary conditions are encountered, the operator has the option to propose an alternative test or monitoring procedures. The request must be submitted by the operator in writing and must be approved in writing by the UIC-Implementation Section Chief or equivalent level of management.

Attachment



Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program, UIC Direct Implementation Program 8P-W-GW
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: ____/____/____

Test conducted by: _____

Others present: _____

Well Name: _____	Type: ER SWD	Status: AC TA UC
Field: _____		
Location: _____	Sec: _____ T _____ N/S R _____ E/W	County: _____ State: _____
Operator: _____		
Last MIT: ____/____/____	Maximum Allowable Pressure: _____	PSIG

Is this a regularly scheduled test? ☐ Yes ☐ No

Initial test for permit? ☐ Yes ☐ No

Test after well rework? ☐ Yes ☐ No

Well injecting during test? ☐ Yes ☐ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: _____ psig

MIT DATA TABLE	Test #1	Test #2	Test #3
TUBING PRESSURE			
Initial Pressure	psig	psig	psig
End of test pressure	psig	psig	psig
CASING / TUBING ANNULUS PRESSURE			
0 minutes	psig	psig	psig
5 minutes	psig	psig	psig
10 minutes	psig	psig	psig
15 minutes	psig	psig	psig
20 minutes	psig	psig	psig
25 minutes	psig	psig	psig
30 minutes	psig	psig	psig
minutes	psig	psig	psig
minutes	psig	psig	psig
RESULT	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test ? ☐ Yes ☐ No

UT 20855-06520
Canvasback Federal #13-23-8-17

Spud Date: 4-9-03
Put on Production: 5-6-03

GL: 5147' KB: 5159'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24# *Base USGWS*
LENGTH: 7 jts. (306') *< 80' -*
DEPTH LANDED: 316' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 140 sxs Class "G" cmt mixed, est 1 bbls cmt to surf.


PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 149 jts. (6410')
DEPTH LANDED: 6408' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 320 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ mixed.
CEMENT TOP AT: 290'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 190 jts (6161.60') *80% Cement Bond*
TUBING ANCHOR: 6173.60' KB
NO. OF JOINTS: 1 jts (32.48')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 6208.88' KB
NO. OF JOINTS: 2 jts (64.80')
TOTAL STRING LENGTH: EOT @ 6275.23' w/12' KB

Proposed Injection
Wellbore Diagram



Initial Production: 106BOPD,
74 MCFD, 6 BWPD

FRAC JOB

4-30-03 6253'-6366' Frac CP 4.5 sand as follows:
50,714# 20/40 sand in 475 bbls Viking I-25
fluid. Treated @ avg press of 2044 psi w/avg
rate of 28 BPM. ISIP 2180 psi. Calc flush:
6250 gal. Actual flush: 6174 gal.

4-30-03 5924'-6127' Frac CP/LOLOC sand as follows:
120,483# 20/40 sand in 882 bbls Viking I-25
fluid. Treated @ avg press of 1650 psi w/avg
rate of 28.7. ISIP 1890 psi. Calc
flush: 5922 gal. Actual flush: 5844 gal.

4-30-03 5716'-5809' Frac UPLDOC and BS sands as follows:
47,868# 20/40 sand in 463 bbls Viking I-25
fluid. Treated @ avg press of 1676 psi w/avg
rate of 27.7 BPM. ISIP 1680 psi. Calc flush:
5714 gal. Actual flush: 5639 gal.

5-01-03 5447'-5458' Frac B.5 sands as follows:
34,936# 20/40 sand in 367 bbls Viking I-25
fluid. Treated @ avg 1700 psi w/avg
rate of 27.4 BPM. ISIP 1580 psi. Calc
flush: 5445 gal. Actual flush: 5375 gal.

5-01-03 5129'-5308' Frac D sands as follows:
56,300# 20/40 sand in 489 bbls Viking I-25
fluid. Treated @ avg 1578 psi w/avg rate of
27.2 BPM. ISIP 1495 psi. Calc flush: 5127
gal. Actual flush: 5043 gal.

5-01-03 4786'-4814' Frac PB7 sands as follows:
50,523# 20/40 sand in 478 bbls Viking I-25
fluid. Treated @ avg 1876 psi w/avg rate of
27.8 BPM. ISIP 1720 psi. Calc flush: 4784
gal. Actual flush: 4691 gal.

PERFORATION RECORD

Date	Depth Range	Tool	Holes
4-29-03	6358'-6366'	4 JSPF	32 holes
4-29-03	6348'-6352'	4 JSPF	16 holes
4-29-03	6298'-6304'	4 JSPF	24 holes
4-29-03	6253'-6258'	4 JSPF	20 holes
4-30-03	6123'-6127'	4 JSPF	16 holes
4-30-03	6062'-6071'	4 JSPF	36 holes
4-30-03	6046'-6057'	4 JSPF	44 holes
4-30-03	6025'-6028'	4 JSPF	12 holes
4-30-03	5924'-5932'	4 JSPF	32 holes
4-30-03	5804'-5809'	4 JSPF	20 holes
4-30-03	5716'-5726'	4 JSPF	40 holes
5-01-03	5447'-5458'	4 JSPF	44 holes
5-01-03	5302'-5308'	4 JSPF	24 holes
5-01-03	5225'-5234'	4 JSPF	36 holes
5-01-03	5141'-5145'	4 JSPF	16 holes
5-01-03	5129'-5138'	4 JSPF	36 holes
5-01-03	4786'-4814'	4 JSPF	112 holes



Inland Resources Inc.

Federal 13-23-8-17

306' FSL & 642' FWL

SWSW Section 23-T8S-R17E

Duchesne Co, Utah

API #43-013-32340; Lease #UTU-76239

PBTD @ 6390'

SHOE/TD @ 6408'

- Est. Basal Carbonate Mem. 6418'
- Est. Wasatch Fm. 6543'

020

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU77233

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: Newfield Production Company		7. UNIT or CA AGREEMENT NAME: CANVASBACK UNIT
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84403		8. WELL NAME and NUMBER: CANVASBACK 15-22-8-17
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 2056 FEL 910 FSL		9. API NUMBER: 4301332240
5. PHONE NUMBER: 435 646.3721		10. FIELD AND POOL, OR WILDCAT: Monument Butte
OTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SW/SE, 22, T8S, R17E		COUNTY: Duchesne
		STATE: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	SubDate	TYPE OF ACTION
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE		<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING		<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR		<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS		<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING		<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 05/05/2005	<input type="checkbox"/> CHANGE WELL NAME		<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS		<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS		<input type="checkbox"/> OTHER: -
	<input checked="" type="checkbox"/> CONVERT WELL TYPE		
	<input type="checkbox"/> PLUG BACK		
	<input type="checkbox"/> REPAIR TREAT		
	<input type="checkbox"/> NEW CONSTRUCTION		
	<input type="checkbox"/> GRILLAGE CHANGE		
	<input type="checkbox"/> TEMPORARILY ABANDON		
	<input type="checkbox"/> PLUG BACK		
	<input type="checkbox"/> PLUG BACK (START/STOP)		
	<input type="checkbox"/> PLUG BACK (WELL SITE)		
	<input type="checkbox"/> PLUG BACK - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well was converted from a producing to an injection well on 4/20/05. The rods and tubing anchor were removed and a packer was inserted in bottom hole assembly 5706'. On 4/20/05 Mr. Dan Jackson w/EPA was notified of the intent to conduct a test on the casing. On 4/22/05 the casing was pressured to 1680 psi w/no pressure loss charted in the 1/2 hour test. No governmental agencies were able to witness the test.

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) Krishna Russell

SIGNATURE


Krishna Russell

TITLE: Production Clerk

DATE: 05/05/2005

(This space for State use only)

RECEIVED
MAY 09 2005
DIV. OF OIL, GAS & MINING



Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 4 / 22 / 2005
Test conducted by: Dale Giles
Others present: _____

Well Name: <u>Canvasback 15-22-8-17</u>	Type: ER SWD	Status: AC TA UC
Field: <u>Canvasback unit</u>		
Location: _____ Sec: <u>22</u> T <u>8</u> N <u>15</u> R <u>17</u> E/W County: <u>Duchesne</u> State: <u>UT</u>		
Operator: _____		
Last MIT: _____ / _____ / _____ Maximum Allowable Pressure: _____ PSIG		

Is this a regularly scheduled test? ☐ Yes ☐ No
Initial test for permit? ☒ Yes ☐ No
Test after well rework? ☐ Yes ☐ No
Well injecting during test? ☐ Yes ☐ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0 psig

MIT DATA TABLE		Test #1	Test #2	Test #3
TUBING PRESSURE				
Initial Pressure	<u>300</u> psig	psig	psig	psig
End of test pressure	<u>300</u> psig	psig	psig	psig
CASING / TUBING ANNULUS PRESSURE				
0 minutes	<u>1680</u> psig	psig	psig	psig
5 minutes	<u>1680</u> psig	psig	psig	psig
10 minutes	<u>1680</u> psig	psig	psig	psig
15 minutes	<u>1680</u> psig	psig	psig	psig
20 minutes	<u>1680</u> psig	psig	psig	psig
25 minutes	<u>1680</u> psig	psig	psig	psig
30 minutes	<u>1680</u> psig	psig	psig	psig
_____ minutes	psig	psig	psig	psig
_____ minutes	psig	psig	psig	psig
RESULT	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test ? ☐ Yes ☐ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

021

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other Injection well

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

2056 FEL 910 FSL

SW/SE Section 22 T8S R17E

5. Lease Serial No.

UTU77233

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

CANVASBACK UNIT

8. Well Name and No.

CANVASBACK 15-22-8-17

9. API Well No.

4301332240

10. Field and Pool, or Exploratory Area

Monument Butte

11. County or Parish, State

Duchesne, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Change Status, Put Well
	<input checked="" type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	on Injection

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomplate in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

The above referenced well was put on injection at 2:00 p.m. on 6/24/05.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Mandie Crozier

Signature

Title

Regulatory Specialist

Date

06/27/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED

JUN 29 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/> Injection well		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU77233
2. NAME OF OPERATOR: Newfield Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: CANVASBACK UNIT
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 2056 FEL 910 FSL		8. WELL NAME and NUMBER: CANVASBACK 15-22-8-17
OTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SW/SE, 22, T8S, R17E		9. API NUMBER: 4301332240
		10. FIELD AND POOL, OR WILDCAT: Monument Butte

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION																											
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<table border="0" style="width: 100%;"><tr><td><input type="checkbox"/> ACIDIZE</td><td><input type="checkbox"/> DEEPEN</td><td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td></tr><tr><td><input type="checkbox"/> ALTER CASING</td><td><input type="checkbox"/> FRACTURE TREAT</td><td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td></tr><tr><td><input type="checkbox"/> CASING REPAIR</td><td><input type="checkbox"/> NEW CONSTRUCTION</td><td><input type="checkbox"/> TEMPORARILY ABANDON</td></tr><tr><td><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</td><td><input type="checkbox"/> OPERATOR CHANGE</td><td><input type="checkbox"/> TUBING REPAIR</td></tr><tr><td><input type="checkbox"/> CHANGE TUBING</td><td><input type="checkbox"/> PLUG AND ABANDON</td><td><input type="checkbox"/> VENT OR FLAIR</td></tr><tr><td><input type="checkbox"/> CHANGE WELL NAME</td><td><input type="checkbox"/> PLUG BACK</td><td><input type="checkbox"/> WATER DISPOSAL</td></tr><tr><td><input type="checkbox"/> CHANGE WELL STATUS</td><td><input type="checkbox"/> PRODUCTION (START/STOP)</td><td><input type="checkbox"/> WATER SHUT-OFF</td></tr><tr><td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td><td><input type="checkbox"/> RECLAMATION OF WELL SITE</td><td><input checked="" type="checkbox"/> OTHER: - Step Rate Test</td></tr><tr><td><input type="checkbox"/> CONVERT WELL TYPE</td><td><input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION</td><td></td></tr></table>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Step Rate Test	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION																										
<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL																										
<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON																										
<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR																										
<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR																										
<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL																										
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF																										
<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Step Rate Test																										
<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION																											
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 11/14/2005																												

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

A step rate test was conducted on the subject well on November 10, 2005. Results from the test indicate that the fracture gradient is .741 psi/ft. Therefore, Newfield is requesting that the maximum allowable injection pressure (MAIP) be changed to 1760 psi.


**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD**

NAME (PLEASE PRINT) <u>Cheyenne Batemen</u>	TITLE <u>Well Analyst Foreman</u>
SIGNATURE <u></u>	DATE <u>11/14/2005</u>

(This space for State use only)


NOV 16 2005

Canvasback 15-22-8-17
 Canvasback Unit
 Step Rate Test
 November 10, 2005



Start Pressure: 1505 psi
 Instantaneous Shut In Pressure (ISIP): 1765 psi
 Top Perforation: 5755 feet
 Fracture pressure (P_{fp}): 1760 psi
 FG: 0.741 psi/ft

Step	Rate(bpd)	Pressure(psi)
1	200	1560
2	400	1635
3	600	1710
4	800	1760
5	1000	1760
6	1200	1765



Step Rate Test (SRT) Analysis

Date: 11/14/2005

Operator:

Newfield Production Company

Well:

Canvasback 15-22-8-17

Permit #:

UT20855-06415

Enter the following data :

Specific Gravity (sg) of injectate = 1.005 g/cc
Depth to top perforation (D) = 5755 feet
Top of permitted injection zone depth (blank=use top perforation to calculate fg) = _____ feet
Estimated Formation Parting Pressure (Pfp) from SRT chart = 1760 psi
Instantaneous Shut In Pressure (ISIP) from SRT = 1765 psi
Bottom Hole Parting Pressure (Pbhp) from downhole pressure recorder = _____ psi

Part One - Calculation of Fracture Gradient (fg)

Calculated Fracture Gradient = 0.741 psi/ft.

where: $fg = Pbhp / D$ (Note: this formula uses the downhole recorded bottom hole parting pressure if available) =

D = depth used = 5755

Pbhp used = 4264

Calculated Bottom Hole Parting Pressure (Pbhp) = 4264 psi

to calculate Bottom Hole Parting Pressure (Pbhp) = Formation Fracture Pressure (ISIP or Pfp) + (0.433 * SG * D)

(Uses lesser of ISIP or Pfp) Value used = 1760

Part Two - Calculation of Maximum Allowable Injection Pressure (MAIP)

Maximum Allowable Injection Pressure (MAIP) = 1760 psig

D = depth used = 5755

MAIP = $[fg \cdot (0.433 \cdot SG)] \cdot D = 1760.080$

(rounded to nearest 5 psig)



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
999 18TH STREET - SUITE 200
DENVER, CO 80202-2466
Phone 800-227-8917
<http://www.epa.gov/region08>

DEC - 2 2005

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Mr. Michael Guinn
Vice President - Operations
Newfield Production Company
Route 3 - Box 3630
Myton, UT 84502

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

43,013,32240

RE: UNDERGROUND INJECTION CONTROL (UIC)
Minor Permit Modification
Increase Injection Pressure: No. 1
EPA Permit No. UT20855-06415
Canvasback No. 15-22-8-17
SW SE Sec. 22 - T8S - R17E
Duchesne County, Utah

Dear Mr. Guinn:

The Region VIII Ground Water Program offices of the Environmental Protection Agency (EPA) received from Newfield Production Company (Newfield) the results and analysis of a November 10, 2005 Step-Rate Test (SRT) run on the Canvasback No. 15-22-8-17 enhanced recovery injection well, EPA Permit No. UT20855-06415. Included with the results was a request to increase the maximum allowable injection pressure (MAIP) from 1755 psig to 1760 psig.

EPA has reviewed the Permit File, and the submitted SRT information show that the formation parting pressure of the injection zone was reached under the conditions recorded during the test. Based upon this test and the EPA analysis, the Director has determined that a pressure of 1760 psig, measured at the surface, is appropriate to ensure that injection does not initiate new fractures or propagate existing fractures in the confining zone overlying the injection zones, and underground sources of drinking water (USDW) will continue to be protected.

DEC 07 2005



Printed on Recycled Paper


Therefore, pursuant to 40 CFR §144.41 (e), the EPA hereby modifies EPA Permit No. 20855-06415 and **authorizes a MAIP of 1760 psig** for the Canvasback No. 15-22-8-17 enhanced recovery injection well.

Should Newfield in the future choose to request a modification to the approved MAIP, new supporting data such as a new SRT will be required as part of your request. In order to inject at pressures greater than the permitted MAIP during any future test(s), the permittee must receive prior authorization from the Director.

If you have any questions in regard to the above action, please contact Dan Jackson of my staff by calling 303-312-6155, or 1-800-227-8917 (Ext. 6155).

Please send all compliance correspondence relative to this well to the **ATTENTION: NATHAN WISER**, at the letterhead address citing **MAIL CODE: 8ENF-UFO** very prominently. You may call Mr. Wiser at 303-312-6211, or 1-800-227-8917 (Ext. 6211).

Sincerely,



for Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

cc: Maxine Natchees
Acting Chairperson
Uintah & Ouray Business Committee
Ute Indian Tribe

Elaine Willie
Environmental Coordinator
Ute Indian Tribe

Chester Mills
Superintendent
Bureau of Indian Affairs
Uintah & Ouray Indian Agency

David Gerbig
Operations Engineer
Newfield Production Company
Denver, Colorado

Gil Hunt
Technical Services Manager
State of Utah - Natural Resources

Matt Baker
Petroleum Engineer
Bureau of Land Management
Vernal District

Nathan Wiser
8ENF-UFO.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NUMBER: USA UTU-77233
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GMBU
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 910 FSL 2056 FEL		8. WELL NAME and NUMBER: CANVASBACK 15-22-8-17
5. PHONE NUMBER: 435.646.3721		9. API NUMBER: 4301332240
6. OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SWSE, 22, T8S, R17E		10. FIELD AND POOL, OR WILDCAT: MONUMENT BUTTE
		COUNTY: DUCHESNE
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA


TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 04/14/2010	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Five Year MIT
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 04-06-2010 Nathan Wiser with the EPA was contacted concerning the 5 year MIT on the above listed well. Permission was given at that time to perform the test on 04-12-2010. On 04-14-2010 the casing was pressured up to 1340 psig and charted for 30 minutes with no pressure loss. The well was injecting during the test. The tubing pressure was 1697 psig during the test. There was not an EPA representative available to witness the test.

EPA# UT 20855-06415 API# 43-013-32240

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) <u>Lucy Chavez-Naupoto</u>	TITLE <u>Administrative Assistant</u>
SIGNATURE 	DATE <u>04/16/2010</u>

(This space for State use only)

RECEIVED
APR 20 2010
DIV. OF OIL, GAS & MINING

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 04/14/10
Test conducted by: Dale Giles
Others present: _____

Well Name: <u>Canvasback 15-22-8-17</u>		Type: ER SWD	Status: AC TA UC
Field: _____			
Location: _____	Sec: <u>22</u> T <u>8</u> N <u>18</u> R <u>17</u> E	W County: <u>Duchesne</u>	State: <u>UT</u>
Operator: <u>Newfield Production Co.</u>			
Last MIT: <u>/</u> <u>/</u> <u>/</u>	Maximum Allowable Pressure: <u>1760</u>		PSIG

Is this a regularly scheduled test? ☒ Yes ☐ No
Initial test for permit? ☐ Yes ☒ No
Test after well rework? ☐ Yes ☒ No
Well injecting during test? ☒ Yes ☐ No If Yes, rate: 15 bpd

Pre-test casing/tubing annulus pressure: 0 psig

MIT DATA TABLE	Test #1	Test #2	Test #3
TUBING PRESSURE			
Initial Pressure	<u>1697</u> psig	psig	psig
End of test pressure	<u>1697</u> psig	psig	psig
CASING / TUBING ANNULUS PRESSURE			
0 minutes	<u>1340</u> psig	psig	psig
5 minutes	<u>1340</u> psig	psig	psig
10 minutes	<u>1340</u> psig	psig	psig
15 minutes	<u>1340</u> psig	psig	psig
20 minutes	<u>1340</u> psig	psig	psig
25 minutes	<u>1340</u> psig	psig	psig
30 minutes	<u>1340</u> psig	psig	psig
_____ minutes	psig	psig	psig
_____ minutes	psig	psig	psig
RESULT	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____




CHART POOL USA
PORTAGE, INDIANA
(TO FIT)
CHART NO. MP-2500
METER _____
04-14-10

CHART PUT ON 10:00 AM
TAKEN OFF 10:30 AM
LOCATION Canastota
REMARKS 15-22-8-17

Dale

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-77233
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: CANVASBACK 15-22-8-17
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0910 FSL 2056 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 22 Township: 08.0S Range: 17.0E Meridian: S		9. API NUMBER: 43013322400000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 3/17/2015	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input type="text" value="5 YR MIT"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. 5 YR MIT performed on the above listed well. On 03/17/2015 the casing was pressured up to 1087 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbq pressure was 1343 psig during the test. There was not an EPA representative available to witness the test. EPA #UT22197-06415		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto		PHONE NUMBER 435 646-4874
SIGNATURE N/A		TITLE Water Services Technician
DATE 3/23/2015		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY March 24, 2015

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____

Date: 3/17/15Test conducted by: Dale Giles

Others present: _____

Well Name: Canvasback 15-22-8-17 Type: ER SWD Status: AC TA UC
Field: Monument Butte
Location: SW/SE Sec: 22 T 8 N/S R 17 E/W County: Duchesne State: ut.
Operator: Newfield production co
Last MIT: 1 Maximum Allowable Pressure: 1950 PSIG

Is this a regularly scheduled test?

☒ Yes ☐ No

Initial test for permit?

☐ Yes ☒ No

Test after well rework?

☐ Yes ☒ No

Well injecting during test?

☒ Yes ☐ NoIf Yes, rate: 13 bpdPre-test casing/tubing annulus pressure: 0 psig

MIT DATA TABLE

	Test #1	Test #2	Test #3
TUBING	PRESSURE		
Initial Pressure	<u>1343</u> psig	psig	psig
End of test pressure	<u>1343</u> psig	psig	psig
CASING / TUBING	ANNULUS PRESSURE		
0 minutes	<u>1083</u> psig	psig	psig
5 minutes	<u>1085</u> psig	psig	psig
10 minutes	<u>1086</u> psig	psig	psig
15 minutes	<u>1087</u> psig	psig	psig
20 minutes	<u>1087</u> psig	psig	psig
25 minutes	<u>1087</u> psig	psig	psig
30 minutes	<u>1087</u> psig	psig	psig
_____ minutes	psig	psig	psig
_____ minutes	psig	psig	psig
RESULT	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No


MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____

Canvasback 15-22-8-17 (5 year MIT)

3/17/2015 8:17:01 AM



NEWFIELD



Schematic

43-013-32240

Well Name: Canvasback 15-22-8-17

Surface Legal Location 22-8S-17E				API/UWI 43013322400000	Well RC 500151545	Lease	State/Province Utah	Field Name GMBU CTB7	County Duchesne
Spud Date 2/21/2003	Rig Release Date 3/24/2003	On Production Date 4/24/2003	Original KB Elevation (ft) 5,180	Ground Elevation (ft) 5,168	Total Depth All (TVD) (ftKB)		PBTD (All) (ftKB) Original Hole - 6,318.0		

Most Recent Job

Job Category Testing	Primary Job Type	Secondary Job Type N/A	Job Start Date 3/17/2015	Job End Date 3/17/2015
-------------------------	------------------	---------------------------	-----------------------------	---------------------------

TD: 6,318.0

Vertical - Original Hole, 3/3/2016 3:06:58 PM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	Vertical schematic (actual)	
			DLS (°... 0 — 3		
12.1	12.1	0.0			
309.1	309.1	0.3			
310.0	310.0	0.3			1; Surface: 8 5/8 in; 8.097 in; 12-310 ftKB; 298.08 ft
399.9	399.9	0.5			
5,701.4	5,690.5	1.2			3-1; Tubing; 2 7/8; 2,441; 12-5,701; 5,689.37
5,702.4	5,691.5	1.2			3-2; Pump Seating Nipple; 2 7/8; 2,441; 5,701-5,702; 1.10
5,710.0	5,699.0	1.3			3-3; AS1 Packer; 5 1/2; 2,441; 5,702-5,710; 7.40
5,754.9	5,743.9	1.5			
5,758.9	5,747.9	1.5			Perforated; 5,755-5,759; 4/21/2003
5,773.0	5,762.0	1.5			Perforated; 5,773-5,777; 4/21/2003
5,776.9	5,765.9	1.6			
6,054.1	6,043.0	1.2			Perforated; 6,054-6,061; 4/21/2003
6,061.0	6,049.9	1.2			
6,084.0	6,072.9	1.0			Perforated; 6,084-6,090; 4/21/2003
6,089.9	6,078.8	0.9			
6,094.2	6,083.1	0.9			Perforated; 6,094-6,105; 4/21/2003
6,105.0	6,093.9	0.8			
6,158.1	6,147.0	0.6			Perforated; 6,158-6,171; 4/14/2003
6,170.9	6,159.8	0.5			
6,205.1	6,193.9	0.4			Perforated; 6,205-6,214; 4/14/2003
6,213.9	6,202.8	0.5			
6,215.9	6,204.8	0.5			Perforated; 6,216-6,227; 4/14/2003
6,227.0	6,215.9	0.5			
6,281.8	6,270.7	0.7			
6,282.2	6,271.0	0.7			
6,285.1	6,274.0	0.7			Perforated; 6,285-6,295; 4/21/2003
6,294.9	6,283.8	0.7			
6,299.2	6,288.1	0.8			
6,299.9	6,288.8	0.8			2; Production; 5 1/2 in; 4.950 in; 12-6,300 ftKB; 6,287.92 ft
6,315.0	6,303.8	0.8			
6,317.9	6,306.8	0.8			

NEWFIELD



Newfield Wellbore Diagram Data Canvasback 15-22-8-17

Surface Legal Location 22-8S-17E		API/UWI 43013322400000		Lease	
County Duchesne	State/Province Utah	Basin		Field Name GMBU CTB7	
Well Start Date 2/21/2003		Spud Date 2/21/2003		Final Rig Release Date 3/24/2003	
Original KB Elevation (ft) 5,180		Ground Elevation (ft) 5,168		On Production Date 4/24/2003	
Total Depth (ftKB) 6,318.0		Total Depth All (TVD) (ftKB)		PBTD (All) (ftKB) Original Hole - 6,318.0	

Casing Strings

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	2/21/2003	8 5/8	8.097	24.00	J-55	310
Production	3/24/2003	5 1/2	4.950	15.50	J-55	6,300

Cement

String: Surface, 310ftKB 3/6/2003

Cementing Company BJ Services Company	Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 310.1	Full Return?	Vol Cement Ret (bbl)
Fluid Description w/ 2% CaCL2 + 1/4#/sk Cello-Flake	Fluid Type Lead	Amount (sacks) 250	Class G	Estimated Top (ftKB) 12.0

String: Production, 6,300ftKB 3/24/2003

Cementing Company BJ Services Company	Top Depth (ftKB) 400.0	Bottom Depth (ftKB) 6,318.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description w/ 10% gel + 3 % KCL, 3#s /sk CSE + 2# sk/kolseal + 1/4#s/sk Cello Flake	Fluid Type Lead	Amount (sacks) 310	Class PL II	Estimated Top (ftKB) 400.0
Fluid Description W/ 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM	Fluid Type Tail	Amount (sacks) 400	Class 50/50 Poz	Estimated Top (ftKB) 3,000.0

Tubing Strings

Tubing Description					Run Date		Set Depth (ftKB)	
Tubing					4/14/2005		5,709.9	
Item Des	Jts	OD (in)	ID (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)
Tubing	177	2 7/8	2.441	6.50	J-55	5,689.37	12.0	5,701.4
Pump Seating Nipple		2 7/8	2.441			1.10	5,701.4	5,702.5
AS1 Packer		5 1/2	2.441			7.40	5,702.5	5,709.9

Rod Strings

Rod Description				Run Date		Set Depth (ftKB)	
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)

Other In Hole

Des	Top (ftKB)	Btm (ftKB)	Run Date	Pull Date
Fill	6,315	6,318	6/7/2004	

Perforation Intervals

Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (")	Nom Hole Dia (in)	Date
3	LODC, Original Hole	5,755	5,759	4			4/21/2003
3	LODC, Original Hole	5,773	5,777	4			4/21/2003
2	CP .5, Original Hole	6,054	6,061	4			4/21/2003
2	CP1, Original Hole	6,084	6,090	4			4/21/2003
2	CP1, Original Hole	6,094	6,105	4			4/21/2003
1	CP2, Original Hole	6,158	6,171	4			4/14/2003
1	CP3, Original Hole	6,205	6,214	4			4/14/2003
1	CP3, Original Hole	6,216	6,227	4			4/14/2003
1	CP4, Original Hole	6,285	6,295	4			4/21/2003

Stimulations & Treatments

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
1	2,020	0.75	27.0	2,100			
2	1,850	0.75	26.0	2,900			
3	1,790	0.74	26.0	3,150			
4							
5							
6							

Proppant

Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
1		Proppant White Sand 98671 lb
2		Proppant White Sand 78834 lb
3		Proppant White Sand 19757 lb
4		



Proppant

Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
5		
6		